

Hydrologic Conditions

for the month of

May 2020

Prepared by the
Hydrologic Data Section
Data Collection Bureau



June 23, 2020

<http://www.watermatters.org>

ACKNOWLEDGMENTS

The Hydrologic Conditions Report is a monthly effort of the Data Collection Bureau's Hydrologic Data Section. Acknowledgment is made to the following staff for their significant contributions, hard work and dedication to the timely production of this report:

Data Collection:	Terry Burrell, Dave Goldberg-Dunnett, Don Everson, George Prine, James Ferrell, Greg Johnston, Everett Eldridge, Robert Noland, Aaron Cronk, James Thomas and Grayson Conklin.
QA/QC and Reporting:	Margit Crowell, Steve DeSmith, Asmita Shukla, Hannah Kolb and Joey Fogel.
Administrative Support/ Document Preparation:	Karen Diez, Lora Caruso and Shelley Browning.

TABLE OF CONTENTS

Introduction	1
Executive Summary – Provisional.....	2
Executive Summary	3
Regional Overview	5
Rainfall	6 - 15
Surface Water	
Lakes.....	16 - 23
Streams.....	24 - 28
Springs.....	29 - 32
Ground Water	
Description of Groundwater Monitoring.....	33
Surficial Aquifer	34 - 35
Intermediate and Floridan Aquifers	36 - 46
Public Supply Wellfields	47 - 48
Aquifer Resource.....	49 - 50
Water Demand	
Public Supply Surface Water Reservoirs.....	51 - 52
Reservoirs.....	53 - 58
Appendices	
Rainfall Percentiles by Intervals & Region.....	59 - 60
Rainfall Grid (NEXRAD).....	61
Lake Monitoring Stations.....	62 - 67
Stream Monitoring Stations.....	68 - 69
Description of Stream Monitoring Stations	70 - 73
Springs Monitoring Stations	74 - 75
Description of Springs Monitoring Stations.....	76 - 77
Surficial Aquifer Monitoring Stations.....	78 - 79
Groundwater & Aquifer Resource Monitoring Stations.....	80 - 81
Wellfield Groundwater Monitoring Stations	82 - 84
Reservoir Locations.....	85


INTRODUCTION

The Hydrologic Conditions Report is generated monthly by the Hydrologic Data Section, Data Collection Bureau, of the Southwest Florida Water Management District. This report provides an end-of-month analytical summary of regional and temporal variations in the hydrologic conditions across the District's 16-county area for planning and regulatory purposes. In addition, it provides an excellent historical record for long-term local and regional hydrologic analysis.

The Hydrologic Data Section is responsible for the implementation and maintenance of a network of observation and monitoring stations used to track changes in various hydrologic parameters over time. Data collected are used by the regulatory, technical, and analytical sections of the District. Data recently collected and maintained by the section include: station and basin rainfall totals, stream and spring discharge measurements, and surface and ground water levels. Frequency of data collection ranges from hourly to monthly readings. All data collected are processed and analyzed, then uploaded into the Water Management Data Base for general access by the District. The Water Management Data Base is also periodically augmented from the United States Geological Survey's hydrologic data network.


The data presented in this report are monthly rainfall totals, streamflow, springflow, surface and ground water levels, reservoir levels and the Aquifer Resource Index. Associated maps of station locations are at the end of the report in the Appendices. Also reported herein are levels of public supply surface water reservoirs supplemented by various regional utilities. The data contained in this report was collected and analyzed in accordance with generally accepted procedures consistent with applicable scientific and technical standards of practice. The data presented are considered to be the best available at the time of publication and are subject to revision. Any questions about the significance, accuracy, or interpretation of these data should be referred to Granville Kinsman, Manager of the Hydrologic Data Section at (352) 796-7211 or (800) 423-1476, extension 4284.

The data evaluation, analyses and interpretation contained within this report have been prepared or approved by a certified Professional Geologist in accordance with Chapter 492, Florida Statutes.



06/18/2020

Registration #PG-1704



Americans with Disabilities Act (ADA)

The Southwest Florida Water Management District (District) does not discriminate on the basis of disability. This nondiscrimination policy involves every aspect of the District's functions, including access to and participation in the District's programs, services and activities. Anyone requiring reasonable accommodation, or would like information as to the existence and location of accessible services, activities, and facilities, as provided for in the Americans with Disabilities Act, should contact Donna Kaspari, Sr. Performance Management Professional, at 2379 Broad St., Brooksville, FL 34604-6899; telephone (352) 796-7211 or 1-800-423-1476 (FL only), ext. 4706; or email ADACoordinator@WaterMatters.org. If you are hearing or speech impaired, please contact the agency using the Florida Relay Service, 1-800-955-8771 (TDD) or 1-800-955-8770 (Voice). If requested, appropriate auxiliary aids and services will be provided at any public meeting, forum, or event of the District. In the event of a complaint, please follow the grievance procedure located at WaterMatters.org/ADA.

EXECUTIVE SUMMARY

Provisional Hydrologic Conditions as of June 17, 2020

Provisional rainfall totals are provided for the period of June 1, 2020 through June 16, 2020. The northern region has received 6.41 inches of rainfall, while the historic mean for the northern region for the month of June is 7.56 inches. The central region has received 6.40 inches of rainfall, while the historic mean for the central region for June is 7.35 inches. The southern region has received 6.52 inches of rainfall, while the historic mean for the southern region for June is 8.23 inches. District-wide, 6.44 inches of rainfall has been received, while the historic mean for the District for June is 7.76 inches.

Provisional lake level data indicate that during the first 16 days of June, regional water levels have increased in all four lake regions of the District, compared to last month's data. Average lake levels in the Northern region increased an average of 0.50 foot and were 0.57 foot below the base of the normal range. Average lake levels in the Tampa Bay region increased an average of 0.60 foot and were 0.75 foot above the base of the normal range. Lake levels in the Polk Uplands region increased 0.44 foot and were 1.42 feet above the base of the normal range. The Lake Wales Ridge region posted an average increase of 0.86 foot and were 0.50 foot below the base of the normal range.

As of June 16, 2020, provisional streamflow data indicates that based on the three regional index rivers referenced below, average streamflow has increased in all three regions of the District, compared to last month's data. Normal streamflow is flow that falls on or between the 25th and 75th percentiles. The average streamflow for the Withlacoochee River near Holder in the northern region was within the normal range at the 41st percentile. The average streamflow for the Hillsborough River near Zephyrhills in the central region was at the upper-end of the normal range at the 70th percentile, while flow in the Peace River at Arcadia in the southern region was above-normal at the 81st percentile.

Provisional groundwater data, as of June 15, 2020, indicate that levels in the intermediate and Floridan aquifers have increased in all three regions of the District, compared to last month's data. Normal aquifer levels are considered levels that fall on or between the 25th and 75th percentiles. Aquifer levels for the northern counties were within the normal range at the 67th percentile, while levels in the central and southern counties were above-normal at the 85th and 92nd percentiles, respectively.

EXECUTIVE SUMMARY

Hydrologic Conditions for May 2020

In May, average rainfall totals were within the normal range in all three regions of the District. The normal range for rainfall is defined by totals that fall on or between the 25th to 75th percentiles of the historical monthly accumulation for each region and where the 50th percentile represents the historical mean. The northern region received an average of 2.46 inches of rainfall, equivalent to the 34th percentile of the historical May record, the central region received an average of 3.06 inches of rainfall, equivalent to the 56th percentile, while the southern region received an average of 4.38 inches of rainfall, equivalent to the 70th percentile. The District-wide rainfall average of 3.35 inches was equivalent to the 56th percentile.

During the eight-month “dry season,” the period from October 1, 2019 through May 31, 2020, rainfall totals for all three regions of the District were within the normal range. The northern region received an average of 21.71 inches of rainfall, which was 1.63 inches below the historical “dry season” mean rainfall of 23.34 inches. This rainfall average was equivalent to the 44th percentile of historical “dry season” mean rainfall and is classified as “normal.” The central region received an average of 22.39 inches of rainfall, which was 0.75 inch above the historical mean of 21.64 inches. This rainfall average was equivalent to the 57th percentile of the historical “dry season” mean rainfall and is classified as “normal.” The southern region received an average rainfall accumulation of 21.04 inches, which was 0.36 inch above the historical mean of 20.68 inches. This rainfall average was equivalent to the 53rd percentile of the historical “dry season” mean rainfall and is classified as “normal.” District-wide, the “dry season” average rainfall was 21.73 inches, which was 0.05 inch below the historical “dry season” mean rainfall of 21.78 inches. This rainfall average was equivalent to the 51st percentile of the historical “dry season” mean rainfall and is classified as “normal.”

During the 12-month period from June 1, 2019 through May 31, 2020, the average rainfall totals in all three regions of the District was classified as “normal.” The northern region received an average of 54.83 inches of rainfall, equivalent to the 56th percentile of the historical annual record. The central region received an average of 54.15 inches of rainfall, equivalent to the 61st percentile, while the southern region received an average of 48.82 inches of rainfall, equivalent to the 37th percentile. The District-wide rainfall average of 52.47 inches was equivalent to the 50th percentile of the historical annual record.

Average lake levels in May were below the annual normal range in the Northern and Lake Wales Ridge regions of the District, while levels were within the annual normal range in the Tampa Bay and Polk Uplands regions. Normal lake levels are defined as levels that fall between the minimum low management level and the minimum flood level. Lake levels in the Northern region decreased by an average of 0.49 foot and were 1.07 feet below the base of the annual normal range. Lake levels in the Tampa Bay region decreased an average of 0.37 foot and were 0.15 foot above the base of the annual normal range. Lake levels in the Polk Uplands region decreased by an average of 0.35 foot and were 0.98 foot above the base of the annual normal range. Lake levels in the Lake Wales Ridge region decreased by an average of 0.39 foot and ended the month 1.36 feet below the base of the annual normal range.

Total streamflow in May, based on the three regional index rivers indicated below, was within the normal range in all three regions of the District. Normal streamflow is defined as the flow that falls on or between the 25th and 75th percentiles. Streamflow measured at the Withlacoochee River near Holder station in the northern region was in the 30th percentile. Streamflow measured at the Hillsborough River near Zephyrhills station in the central region was in the 30th percentile, while streamflow measured at the Peace River at Arcadia station in the southern region was in the 37th percentile.

In May, groundwater data showed that levels in the intermediate and Floridan aquifers ended the month within the normal range in the northern and central counties of the District, while levels were above-normal in the southern counties. The normal range is defined as the level that falls on or between the 25th and 75th percentiles. The groundwater level in the northern, central and southern counties were in the 51st, 67th and 84th percentiles, respectively.

REGIONAL OVERVIEW OF HYDROLOGIC CONDITIONS

MAY 2020

Northern Region

In May, the northern region received an average of 2.46 inches of rainfall, equivalent to the 34th percentile of the historical May readings, which is considered "normal." Average lake levels decreased in the northern region and ended the month an average of 1.07 feet below the base of the annual normal range. Total streamflow measured in the Withlacoochee River near Holder station decreased and was in the 30th percentile. Regional groundwater levels indicated average surficial aquifer water levels decreased and were in the 53rd percentile, while levels in the intermediate and Floridan aquifer decreased and were in the 51st percentile.

Central Region

In May, the central region received an average of 3.06 inches of rainfall, equivalent to the 56th percentile of historical May readings, which is considered "normal." Average lake levels decreased in the Tampa Bay and Polk Uplands regions, ending the month 0.15 and 0.98 foot, respectively, above the base of the annual normal range. Total streamflow measured at the Hillsborough River near Zephyrhills station decreased and was in the 30th percentile. Regional groundwater levels indicated average surficial aquifer water levels decreased and were in the 61st percentile, while levels in the intermediate and Floridan aquifer increased and were in the 67th percentile.

Southern Region

In May, the southern region received an average of 4.38 inches of rainfall, equivalent to the 70th percentile of historical May readings, which is considered "normal." Average lake levels decreased in the Lake Wales Ridge region and ended the month 1.36 feet below the base of the annual normal range. Total streamflow measured at the Peace River at Arcadia station decreased and was in the 37th percentile. Regional groundwater levels indicated average surficial aquifer water levels decreased and were in the 34th percentile, while levels in the intermediate and Floridan aquifer increased and were in the 84th percentile.

RAINFALL

The rainfall data used for all tabulations in this report are provided to the District under contract with an external vendor. These data are created by enhancing contractor-developed NEXRAD radar rainfall imagery with 15-minute rainfall data collected from the District's network of real-time gauges. This process results in highly accurate cell-based rainfall data representative of conditions over the entire District, including those portions where rainfall data collection would otherwise be limited due to gaps in the gauging network.

As defined by the United States Geological Survey (USGS), a percentile is a value on a scale of one hundred that indicates the percent of a distribution that is equal to or below it. For example, a rainfall total equivalent to the 90th percentile is equal to or greater than 90 percent of the rainfall totals recorded for this month during all years that totals have been recorded.

Percentiles for rainfall were calculated from the historical record by region, and by specific interval. The "wet season" total is the sum of the rainfall from June through September. The "dry season" total is the sum of the rainfall from October through May. The annual total characterization was calculated from a dataset of moving 12-month rainfall sum for the same period (1915 through the most recent completed year). The moving 12-month rainfall sum was used for annual statistics because it provided a much larger dataset, and therefore a better estimate of the true percentiles. The historical 12-month cumulative average is updated monthly.

Characterization ranges were established for each region, and for the whole District, with breaks at the 10th (P10), the 25th (P25), the 75th (P75) and the 90th (P90) percentiles. The rainfall in inches for each percentile break, by rainfall interval and by region and the characterization ranges are summarized in the Appendix.

In May, rainfall totals were within the normal range in all three regions of the District. The normal range for rainfall is defined by totals that fall on or between the 25th to 75th percentiles of the historical monthly average for each region and where the 50th percentile represents the historical mean. The northern region received an average of 2.46 inches of rainfall, equivalent to the 34th percentile of the historical May record. The central region received an average of 3.06 inches, equivalent to the 56th percentile of the historical May record, while the southern region received an average of 4.38 inches, equivalent to the 70th percentile. District-wide, rainfall averaged 3.35 inches, which is equivalent to the 56th percentile.

During the eight-month "dry season," the period from October 1, 2019 through May 31, 2020, rainfall totals for all three regions of the District were within the normal range. The northern region received an average of 21.71 inches of rainfall, which was 1.63 inches below the historical "dry season" mean rainfall of 23.34 inches. This rainfall average was equivalent to the 44th percentile of historical "dry season" mean rainfall and is classified as "normal." The central region received an average of 22.39 inches of rainfall, which was 0.75 inch above the historical mean of 21.64 inches. This rainfall average was equivalent to the 57th percentile of the historical "dry season" mean rainfall and is classified as "normal." The southern region received an average rainfall accumulation of 21.04 inches, which was 0.36 inch above the historical mean of 20.68 inches. This rainfall average was equivalent to the

53rd percentile of the historical "dry season" mean rainfall and is classified as "normal." District-wide, the "dry season" average rainfall was 21.73 inches, which was 0.05 inch below the historical "dry season" mean rainfall of 21.78 inches. This rainfall average was equivalent to the 51st percentile of the historical "dry season" mean rainfall and is classified as "normal."

During the 12-month period from June 1, 2019 through May 31, 2020, the average rainfall totals in all three regions and District-wide were classified as "normal." The northern region received an average of 54.83 inches of rainfall, equivalent to the 56th percentile of the historical record. The central region received an average of 54.15 inches of rainfall, equivalent to the 61st percentile. The southern region received an average of 48.82 inches of rainfall, equivalent to the 37th percentile. The District-wide rainfall average was 52.47 inches, which is equivalent to the 50th percentile of the historical annual record.

Tampa Monthly Climate Summary for May 2020

According to the National Weather Service (NWS), the monthly average temperature (°F) for Tampa was 78.9 degrees, which was 0.5 degrees above normal. The highest temperature recorded during the month was 94.0 degrees, while the lowest temperature recorded during the month was 58.0 degrees. The May 2020 monthly high temperature of 78.9 degrees ties with 2004 and 1946 as the 24th warmest May since records began in 1890. The warmest May had an average temperature of 81.7 degrees, which occurred in 1995.

Temperature and Precipitation Outlook

The Climate Prediction Center's (CPC) three-month weather forecast, as of June 18, 2020, indicates above-normal chances for rainfall throughout the District during the composite 3-month period from July through September 2020. The temperature forecast for this same time-period indicates above-normal temperatures throughout the District.

For more information log on to the CPC's website at:

http://www.cpc.ncep.noaa.gov/products/OUTLOOKS_index.html

RELATIONSHIP OF MAY 2020 RAINFALL TO HISTORICAL RAINFALL AVERAGES

Regional Summary:

<i>Region</i>	<i>MAY 2020 Average Rainfall</i>	<i>Historical Average for MAY</i>	<i>Departure from Historical Average</i>	<i>Calendar Year 2020 Cumulative Rainfall JAN-MAY</i>	<i>Calendar Year Historical Cumulative Rainfall JAN-MAY</i>	<i>Departure from Historical Cumulative MAY 2020</i>	<i>Cumulative 12-month Rainfall JUN 2019- MAY 2020</i>	<i>Historical 12-month Cumulative Rainfall</i>	<i>Departure from Historical 12-month Cumulative</i>
Northern Counties	2.46	3.68	-1.22	10.72	15.97	-5.25	54.83	53.61	1.22
Central Counties	3.06	3.40	-0.34	10.68	14.59	-3.91	54.15	52.43	1.72
Southern Counties	4.38	3.72	0.66	12.74	13.93	-1.19	48.82	52.41	-3.59
District All Counties	3.35	3.59	-0.24	11.40	14.74	-3.34	52.47	52.75	-0.28

Regional Counties Summary:

<i>NORTHERN COUNTIES</i>	<i>MAY 2020 Average Rainfall</i>	<i>Historical Average for MAY</i>	<i>Departure from Historical Average</i>	<i>Calendar Year 2020 Cumulative Rainfall JAN-MAY</i>	<i>Calendar Year Historical Cumulative Rainfall JAN-MAY</i>	<i>Departure from Historical Cumulative MAY 2020</i>	<i>Cumulative 12-month Rainfall JUN 2019- MAY 2020</i>	<i>Historical 12-month Cumulative Rainfall</i>	<i>Departure from Historical 12-month Cumulative</i>
Levy County	2.64	3.27	-0.63	11.22	16.53	-5.31	57.17	54.01	3.16
Marion County	2.80	3.74	-0.94	11.13	16.61	-5.48	52.01	54.34	-2.33
Citrus County	2.10	3.60	-1.50	10.03	15.88	-5.85	56.37	54.12	2.25
Sumter County	2.57	3.75	-1.18	10.48	15.74	-5.26	52.58	51.95	0.63
Hernando County	2.10	3.70	-1.60	11.00	15.93	-4.93	56.86	55.04	1.82
<i>CENTRAL COUNTIES</i>									
Pasco County	2.44	3.64	-1.20	10.96	15.52	-4.56	55.37	54.08	1.29
Pinellas County	1.67	2.89	-1.22	9.95	13.98	-4.03	57.27	51.75	5.52
Hillsborough County	2.35	3.58	-1.23	10.21	14.60	-4.39	53.36	52.69	0.67
Polk County	4.10	4.16	-0.06	10.99	15.05	-4.06	53.55	52.03	1.52
<i>SOUTHERN COUNTIES</i>									
Manatee County	3.40	3.29	0.11	12.16	13.80	-1.64	51.07	53.44	-2.37
Hardee County	4.77	3.99	0.78	13.04	14.13	-1.09	49.81	52.13	-2.32
Highlands County	6.98	4.14	2.84	15.23	14.04	1.19	51.21	52.01	-0.80
Sarasota County	3.80	3.19	0.61	12.67	13.31	-0.64	48.62	52.68	-4.06
DeSoto County	4.86	3.88	0.98	13.38	13.53	-0.15	45.82	51.87	-6.05
Charlotte County	3.62	3.61	0.01	10.65	12.83	-2.18	46.13	52.58	-6.45

MAY 2020 RAINFALL CHARACTERIZATION

Regional Characterization:

<i>Region</i>	<i>MAY 2020 Average Rainfall</i>	<i>Historical MAY Percentile</i>	<i>MAY Rainfall Characterization</i>	<i>Cumulative 12-month Rainfall JUN 2019- MAY 2020</i>	<i>Historical 12-month Cumulative Percentile</i>	<i>12-month Cumulative Rainfall Characterization</i>
Northern Counties	2.46	34	Normal	54.83	56	Normal
Central Counties	3.06	56	Normal	54.15	61	Normal
Southern Counties	4.38	70	Normal	48.82	37	Normal
District Counties	3.35	56	Normal	52.47	50	Normal

Regional Counties Characterization:

<i>NORTHERN COUNTIES</i>	<i>MAY 2020 Average Rainfall</i>	<i>Historical MAY Percentile</i>	<i>MAY Rainfall Characterization</i>	<i>Cumulative 12-month Rainfall JUN 2019- MAY 2020</i>	<i>Historical 12-month Cumulative Percentile</i>	<i>12-month Cumulative Rainfall Characterization</i>
Levy County	2.64	46	Normal	57.17	67	Normal
Marion County	2.80	45	Normal	52.01	39	Normal
Citrus County	2.10	35	Normal	56.37	60	Normal
Sumter County	2.57	37	Normal	52.58	52	Normal
Hernando County	2.10	31	Normal	56.86	60	Normal
<i>CENTRAL COUNTIES</i>						
Pasco County	2.44	39	Normal	55.37	57	Normal
Pinellas County	1.67	35	Normal	57.27	74	Normal
Hillsborough County	2.35	33	Normal	53.36	55	Normal
Polk County	4.10	60	Normal	53.55	58	Normal
<i>SOUTHERN COUNTIES</i>						
Manatee County	3.40	62	Normal	51.07	42	Normal
Hardee County	4.77	68	Normal	49.81	42	Normal
Highlands County	6.98	89	Wetter than normal	51.21	48	Normal
Sarasota County	3.80	71	Normal	48.62	35	Normal
DeSoto County	4.86	72	Normal	45.82	29	Normal
Charlotte County	3.62	57	Normal	46.13	27	Normal

RELATIONSHIP OF DRY SEASON (OCT 2019 to MAY 2020) RAINFALL TO HISTORICAL DRY SEASON RAINFALL


Regional Characterization:

<i>Region</i>	<i>Dry Season Rainfall OCT 2019- MAY 2020</i>	<i>Historical Dry Season Rainfall Average</i>	<i>Departure from Historical Rainfall Average</i>	<i>Historical Dry Season Percentile</i>	<i>Dry Season Rainfall Characterization OCT 2019- MAY 2020</i>
Northern Counties	21.71	23.34	-1.63	44%	Normal
Central Counties	22.39	21.64	0.75	57%	Normal
Southern Counties	21.04	20.68	0.36	53%	Normal
District Counties	21.73	21.78	-0.05	51%	Normal


Regional Counties Characterization:

<i>NORTHERN COUNTIES</i>	<i>Dry Season Rainfall OCT 2019- MAY 2020</i>	<i>Historical Dry Season Rainfall Average</i>	<i>Departure from Historical Rainfall Average</i>	<i>Historical Dry Season Percentile</i>	<i>Dry Season Rainfall Characterization OCT 2019- MAY 2020</i>
Levy County	21.55	24.38	-2.83	42%	Normal
Marion County	20.27	24.36	-4.09	33%	Normal
Citrus County	20.40	23.17	-2.77	43%	Normal
Sumter County	22.39	22.92	-0.53	50%	Normal
Hernando County	23.26	23.32	-0.06	51%	Normal
<i>CENTRAL COUNTIES</i>					
Pasco County	23.24	22.79	0.45	54%	Normal
Pinellas County	22.77	21.18	1.59	64%	Normal
Hillsborough County	21.44	21.42	0.02	51%	Normal
Polk County	22.55	21.76	0.79	55%	Normal
<i>SOUTHERN COUNTIES</i>					
Manatee County	20.73	20.67	0.06	52%	Normal
Hardee County	21.78	20.65	1.13	57%	Normal
Highlands County	24.38	20.83	3.55	73%	Normal
Sarasota County	21.33	20.31	1.02	59%	Normal
DeSoto County	20.25	20.24	0.01	54%	Normal
Charlotte County	18.72	19.63	-0.91	49%	Normal

MAY 2020 RAINFALL HISTORIC AVERAGE VS HISTORICAL MAY AVERAGE (INCHES)



MAY 2020 12-MONTH CUMULATIVE RAINFALL VS AVERAGE ANNUAL CUMULATIVE (INCHES)




12-month Cumulative Rainfall



Average 12-month Cumulative

SWFWMD Rainfall Distribution May 2020




Compiled by M.L. Crowell
Data source: Vieux, Inc.

Southwest Florida
Water Management District

SWFWMD Rainfall Distribution

October 2019 through May 2020
Dry Season




Compiled by M. L. Crowell
Data source: Vieux, Inc.

Southwest Florida
Water Management District

SWFWMD Rainfall Distribution

June 2019 through May 2020



Compiled by M.L. Crowell
Data source: Vieux, Inc.

Southwest Florida
Water Management District

SURFACE WATER

Lakes

Across the District, 76 lakes have been selected as excellent indicators of current surface water conditions (see index map in Appendix). Water levels of these lakes are read monthly. In general, these lakes are concentrated in four regions, the northern region of Citrus, Hernando, and Sumter Counties, the Tampa Bay region of Hillsborough and Pasco Counties, the Polk Uplands region of northern Polk County, and the Lake Wales Ridge region of Polk and Highlands Counties. In this report, current monthly lake levels are tabulated and compared with previous records as well as District-established management levels. In addition, lake-level data representative of the four regions are presented in hydrographs showing a 15-year history of water levels, as a general indicator of surface-water conditions in that region.

The District's Governing Board (the Board) has established lake management levels for approximately 410 lakes within District boundaries, which are specified in Chapter 40D-8, Florida Administrative Code (F.A.C.). Management levels help protect the water resources of the District and the ecology of the lake or water-body for which it was established. In this report, the following three management levels are used to indicate normal and low lake levels: the Minimum Flood (MF) level, the Minimum Low Management (MLM) level, and the Minimum Extreme Low Management (MELM) level. In general, the MF level corresponds to the normal high level, the MLM to the normal low level, and the MELM to a drought-year low. These levels were derived from various sources, including technical publications, topographic maps, Water Resource Data Reports of the USGS, and other studies. Field investigations are also used to determine past surface levels from water marks, wetland vegetation, dry land vegetation, and to establish the elevation of septic tanks, docks, sea walls, roads and floor slabs.

During a normal year, each of the indicator lakes should reach both the designated normal high (MF) and the normal low (MLM) levels. In addition, it is generally beneficial for lakes to reach the adopted drought year low (MELM) level every four to six years for a short period of time for the biological health of the lake. In this report, hydrographs of representative lakes compare current and recent water levels against “**normal ranges**” defined by the adopted MF and MLM levels.

Of the 76 lakes presented in this report, 17 have water-control structures. These structures are used for water conservation and do not generally influence the water levels with regard to meteorologically wet or dry conditions. During periods of extreme high water, the structures may be operated to minimize flooding.

During May, 74 of the 76 lakes monitored for this report recorded water level decreases, compared to last month. Data was missing for Camp Lake located in the Tampa Bay region. Water levels decreased in the Northern, Tampa Bay, Polk Uplands and Lake Wales regions by 0.49, 0.37, 0.35 and 0.39 foot, respectively. District-wide, average water levels decreased by 0.39 foot, compared to last month.

In May, 63 of the 76 lakes monitored for this report recorded water level decreases, 11 recorded increases, while one recorded the same level, compared to last year's levels. Data was missing for Camp Lake located in the Tampa Bay region. In the Northern, Tampa Bay, Polk Uplands and Lake Wales Ridge regions, average lake levels were lower by 0.58, 0.41, 0.26 and 0.45 foot, respectively. District-wide, average lake levels were lower by 0.41 foot, compared to last year's levels.

Water levels in 44 of the 76 lakes were above the base of the annual normal range, levels in 30 lakes were below the base, while the level in one lake was equal to the bottom of the annual range. Average lake levels in the Northern and Lake Wales Ridge regions were 1.07 and 1.36 feet, respectively, below the base of the annual normal range, while average lake levels in the Tampa Bay and Polk Uplands regions were 0.15 and 0.98 foot, respectively, above the base of the annual normal range. District-wide, average lake levels were 0.06 foot below the base of the annual normal range. Water levels in 68 of the 76 lakes were above the drought-year levels.

SUMMARY OF LAKE ELEVATIONS OF REGIONAL LAKES (feet)

NORTHERN LAKES															
Lake Name	County	Beginning of Record	APR 2020	MAY 2020	MAY 2019	Change from APR 2020	Change from MAY 2019	Diff from MELM	(MELM) Drought Year Low	(MLM) Normal Year Low	(MF) Normal Year High	Period of Record Low	Record Low Date	Period of Record High	Record High Date
Big Fish Lake	Pasco	1980	72.79	72.55	73.48	-0.24	-0.93	0.80	71.75	73.05	76.05	0.00	FEB 1998	77.40	SEP 2004
Crews Lake	Pasco	1986	50.70	50.24	51.26	-0.46	-1.02	0.24	50.00	52.00	55.00	0.86	APR 2001	54.92	MAR 1998
Hancock Lake	Pasco	1978	100.18	99.50	100.38	-0.68	-0.88	-2.50	102.00	104.00	106.50	0.80	SEP 1982	108.90	MAR 1998
Hunters Lake	Hernando	1967	18.49	17.96	17.27	-0.53	0.69	1.96	16.00	17.50	20.50	11.70	JUN 2001	20.50	MAR 1970
Lake Iola	Pasco	1984	140.47	140.09	139.57	-0.38	0.52	-2.41	142.50	145.00	147.50	128.96	MAY 2012	148.70	JAN 1989
Lake Lindsey	Hernando	1982	65.21	64.77	65.47	-0.44	-0.70	0.27	64.50	66.00	69.00	59.38	MAY 2012	69.47	MAR 1998
Little Lake (Consu	Citrus	1985	37.90	37.24	38.20	-0.66	-0.96	-0.01	37.25	39.00	41.50	31.10	MAY 2001	42.84	SEP 2004
Lake Miona	Sumter	1985	54.57	54.11	53.37	-0.46	0.74	3.11	51.00	53.00	55.00	47.88	MAY 2002	55.37	SEP 2019
Moon Lake	Pasco	1990	39.18	38.87	39.46	-0.31	-0.59	3.37	35.50	37.50	40.50	19.83	JAN 2017	41.26	SEP 2004
Lake Panasoffkee	Sumter	1984	39.84	39.38	39.65	-0.46	-0.27	0.88	38.50	39.50	42.50	0.00	JUL 1994	43.04	OCT 2004
Lake Pasadena	Pasco	1984	91.27	90.69	91.41	-0.58	-0.72	0.69	90.00	91.50	94.50	81.56	MAY 2001	94.86	OCT 2004
Spring Lake	Hernando	1965	180.03	179.55	180.65	-0.48	-1.10	1.30	178.25	181.25	184.25	174.85	JUN 1965	183.57	OCT 1984
Floral City Pool	Citrus	1981	39.63	38.92	40.06	-0.71	-1.14	0.67	38.25	40.25	42.50	0.83	MAY 2000	42.66	SEP 2004
Inverness Pool	Citrus	1985	38.32	37.84	38.97	-0.48	-1.13	1.59	36.25	38.25	40.50	0.77	MAY 2000	40.89	OCT 2004
Hernando Pool	Citrus	1985	37.25	36.78	38.02	-0.47	-1.24	2.03	34.75	36.75	39.00	0.86	MAY 2000	40.17	FEB 1998

TAMPA BAY LAKES															
Lake Name	County	Beginning of Record	APR 2020	MAY 2020	MAY 2019	Change from APR 2020	Change from MAY 2019	Diff from MELM	(MELM) Drought Year Low	(MLM) Normal Year Low	(MF) Normal Year High	Period of Record Low	Record Low Date	Period of Record High	Record High Date
Lake Alice	Hillsborough	1981	39.62	39.30	40.21	-0.32	-0.91	1.80	37.50	40.25	42.25	19.84	JUN 2017	42.42	SEP 2004
Lake Ann-Parker	Pasco	1983	46.93	46.55	46.78	-0.38	-0.23	1.55	45.00	45.75	48.75	43.28	JUN 2001	49.29	AUG 2015
Bay Lake	Hillsborough	1982	45.76	45.74	43.91	-0.02	1.83	3.24	42.50	44.00	46.75	41.86	APR 1985	46.47	DEC 1997
Lake Brant	Hillsborough	1981	57.16	57.10	57.36	-0.06	-0.26	2.60	54.50	56.50	58.75	0.96	OCT 1994	59.57	AUG 2015
Brooker Lake	Hillsborough	1977	62.34	62.07	62.26	-0.27	-0.19	3.07	59.00	61.00	64.25	56.49	MAY 2002	64.08	DEC 1997
Calm Lake	Hillsborough	1982	48.98	48.67	49.48	-0.31	-0.81	3.67	45.00	47.50	50.50	41.88	JUN 2002	51.04	JUL 2015
Camp Lake	Pasco	1983	M	M	61.60	M	M	M	59.00	61.75	64.00	50.82	MAY 2002	64.05	JUL 2015
Carlton Lake	Hillsborough	1976	93.29	91.17	91.01	-2.12	0.16	3.17	88.00	90.50	93.50	86.82	MAY 2001	94.60	FEB 1998
Lake Carroll	Hillsborough	1985	35.97	35.69	35.72	-0.28	-0.03	3.19	32.50	34.50	37.00	0.90	MAY 1999	37.87	AUG 2015
Church Lake	Hillsborough	1983	34.38	34.08	34.74	-0.30	-0.66	2.58	31.50	34.00	36.25	27.94	MAY 2002	36.90	JUL 1987
Lake Cooper	Hillsborough	1980	59.44	59.23	59.46	-0.21	-0.23	2.23	57.00	59.75	61.75	0.88	SEP 2001	62.44	AUG 2015
Crescent Lake	Hillsborough	1981	41.23	40.96	41.44	-0.27	-0.48	2.46	38.50	40.00	42.50	35.34	JUN 2001	42.89	SEP 2017
Deer Lake	Hillsborough	1977	65.40	64.99	65.88	-0.41	-0.89	2.49	62.50	64.50	67.25	0.90	OCT 2001	67.42	DEC 1997
Egypt Lake	Hillsborough	1978	35.88	35.66	36.18	-0.22	-0.52	3.16	32.50	35.00	37.50	33.06	MAY 2000	38.15	SEP 1985
Gornto Lake	Hillsborough	1979	36.01	35.75	36.29	-0.26	-0.54	1.75	34.00	36.00	38.50	29.86	MAR 1979	39.48	FEB 1998
Lake Harvey	Hillsborough	1984	60.01	60.25	60.36	0.24	-0.11	2.25	58.00	60.25	62.50	53.94	MAY 2002	63.90	DEC 1997
Lake Hiawatha	Hillsborough	1981	49.50	49.29	49.74	-0.21	-0.45	4.29	45.00	48.00	50.50	46.14	JUN 2000	51.12	APR 2010
Horse Lake	Hillsborough	1930	44.51	43.77	45.63	-0.74	-1.86	1.77	42.00	44.00	46.50	0.83	MAR 2000	50.00	AUG 1959
Lake Keene	Hillsborough	1981	61.80	61.17	61.59	-0.63	-0.42	2.17	59.00	60.50	63.00	56.12	JUN 2002	63.69	SEP 2017
Keystone Lake	Hillsborough	1984	40.71	40.10	40.72	-0.61	-0.62	1.10	39.00	39.75	42.00	0.92	MAY 2000	43.64	AUG 2015
King Lake	Pasco	1983	102.21	101.78	101.90	-0.43	-0.12	1.78	100.00	102.50	105.25	94.20	APR 2009	104.80	MAR 1987
Lake Leclare	Hillsborough	1977	50.50	50.28	50.66	-0.22	-0.38	3.28	47.00	49.50	52.00	44.95	JUN 2001	52.99	JUL 2015
Lake Linda	Pasco	1983	64.71	64.43	64.85	-0.28	-0.42	2.43	62.00	64.00	66.75	60.07	MAY 2001	67.17	SEP 2017
Little Lake	Hillsborough	1979	44.60	44.35	44.79	-0.25	-0.44	2.35	42.00	43.50	46.50	38.06	JUN 1994	48.55	JUN 2017
Long Pond	Hillsborough	1978	44.45	44.10	45.00	-0.35	-0.90	2.10	42.00	44.00	46.50	36.33	MAY 1979	48.27	SEP 1998
Mud (Walden) Lake	Hillsborough	1978	112.70	112.51	112.69	-0.19	-0.18	2.01	110.50	112.50	115.00	111.45	MAY 2017	114.42	MAR 1978
Lake Padgett	Pasco	1965	68.68	68.46	68.74	-0.22	-0.28	0.96	67.50	69.00	71.25	66.27	JUN 2001	71.84	SEP 1985
Platt Lake	Hillsborough	1981	48.78	48.43	48.74	-0.35	-0.31	2.43	46.00	47.75	50.50	42.53	JUN 2001	51.61	AUG 2015
Rainbow Lake	Hillsborough	1981	37.89	37.49	38.62	-0.40	-1.13	2.49	35.00	37.50	40.50	29.82	JUN 2002	40.95	JUL 2015
Lake Stemper	Hillsborough	1983	59.89	59.45	59.98	-0.44	-0.53	1.45	58.00	59.50	62.00	53.36	JUN 2001	61.68	SEP 2004
Lake Thomas	Hillsborough	1981	62.08	62.01	62.32	-0.07	-0.31	2.76	59.25	61.25	63.50	56.48	JUN 2002	64.13	AUG 2015
Turkey Ford Lake	Hillsborough	1989	50.31	50.15	50.23	-0.16	-0.08	0.15	50.00	51.50	54.00	48.50	JUN 2000	54.80	JUN 2012
Lake Wimauma	Hillsborough	1985	78.27	77.06	77.77	-1.21	-0.71	-3.94	81.00	83.00	86.75	0.00	OCT 2004	84.38	MAR 1998

NOTE: M='no data' or 'not determined'

All elevations are referenced to NGVD 1929 datum. Report compiled by Hannah Kolb

SUMMARY OF LAKE ELEVATIONS OF REGIONAL LAKES (feet)

POLK UPLANDS LAKES															
Lake Name	County	Beginning of Record	APR 2020	MAY 2020	MAY 2019	Change from APR 2020	Change from MAY 2019	Diff from MELM	(MELM) Drought Year Low	(MLM) Normal Year Low	(MF) Normal Year High	Period of Record Low	Record Low Date	Period of Record High	Record High Date
Lake Alfred	Polk	1990	130.84	130.39	129.36	-0.45	1.03	4.14	126.25	128.25	130.75	0.85	MAR 1998	132.76	MAR 1998
Lake Ariana	Polk	1984	136.17	135.80	136.17	-0.37	-0.37	3.30	132.50	134.50	137.00	1.00	SEP 2004	137.66	JAN 2016
Lake Arietta	Polk	1970	142.02	141.74	141.77	-0.28	-0.03	3.74	138.00	141.00	144.00	0.00	NOV 2000	144.12	SEP 2004
Blue Lake South	Polk	1986	113.85	113.41	111.97	-0.44	1.44	0.91	112.50	114.00	117.00	103.38	FEB 1991	119.19	DEC 2005
Lake Bonny	Polk	1954	129.14	128.67	129.65	-0.47	-0.98	2.67	126.00	128.00	130.50	0.00	MAY 2001	133.08	SEP 2004
Lake Buffum	Polk	1982	130.68	130.36	131.00	-0.32	-0.64	3.61	126.75	129.25	132.25	123.90	JUN 1991	133.00	JUN 2005
Clearwater Lake	Polk	1979	142.93	142.30	143.14	-0.63	-0.84	3.30	139.00	141.00	143.50	137.93	MAY 2001	146.06	AUG 1984
Lake Conine	Polk	1989	128.00	127.62	127.92	-0.38	-0.30	3.12	124.50	126.50	128.75	123.83	NOV 2009	129.95	SEP 2004
Eagle Lake	Polk	1965	128.86	128.51	129.05	-0.35	-0.54	2.01	126.50	128.50	130.75	0.86	SEP 2004	131.50	SEP 1996
Lake Fannie	Polk	1981	124.83	124.50	124.69	-0.33	-0.19	4.50	120.00	123.50	125.75	58.51	JUN 2008	127.51	SEP 2004
Lake Garfield	Polk	1982	100.77	100.49	101.55	-0.28	-1.06	0.49	100.00	101.00	104.75	0.90	SEP 2004	105.70	FEB 1998
Lake Hamilton	Polk	1981	120.53	120.36	120.37	-0.17	-0.01	3.11	117.25	119.00	121.50	111.25	MAR 2008	123.96	OCT 2004
Lake Helene	Polk	1961	144.85	144.37	145.17	-0.48	-0.80	5.37	139.00	141.00	144.00	134.06	JUN 2008	146.71	OCT 2017
Lake Howard	Polk	1987	130.87	130.47	131.11	-0.40	-0.64	3.47	127.00	129.50	132.00	127.69	MAY 2001	133.08	SEP 2004
Lake Juliana	Polk	1984	132.61	132.41	132.23	-0.20	0.18	4.91	127.50	130.00	132.50	127.40	NOV 2009	134.10	MAR 1998
Lake Mcleod	Polk	1983	129.14	128.71	129.23	-0.43	-0.52	0.71	128.00	129.50	132.00	120.76	JUL 1985	131.98	SEP 1998
Lake Otis	Polk	1989	126.60	126.05	126.65	-0.55	-0.60	3.05	123.00	125.00	128.00	0.00	MAY 2001	128.50	SEP 2004
Lake Ruby	Polk	1983	124.15	124.11	124.40	-0.04	-0.29	3.11	121.00	123.00	125.25	120.78	JUN 2001	125.98	SEP 2004
Lake Gibson	Polk	1984	142.50	142.41	142.28	-0.09	0.13	0.91	141.50	141.50	143.50	0.00	MAY 2000	145.40	SEP 1988

LK WALES RIDGE LAKES															
Lake Name	County	Beginning of Record	APR 2020	MAY 2020	MAY 2019	Change from APR 2020	Change from MAY 2019	Diff from MELM	(MELM) Drought Year Low	(MLM) Normal Year Low	(MF) Normal Year High	Period of Record Low	Record Low Date	Period of Record High	Record High Date
Lake Annie	Polk	1983	115.55	115.17	115.17	-0.38	0.00	1.17	114.00	116.00	119.00	108.36	JUN 1990	117.56	OCT 2005
Lake Clay	Highlands	1983	77.47	77.15	77.39	-0.32	-0.24	2.15	75.00	76.00	78.75	74.34	MAY 2001	78.82	JUN 2013
Crooked Lake	Polk	1982	119.43	119.03	117.77	-0.40	1.26	2.03	117.00	118.50	122.00	106.28	APR 1991	123.44	AUG 2005
Lake Jackson	Highlands	1984	101.27	100.87	101.23	-0.40	-0.36	2.87	98.00	100.00	103.00	96.47	JUN 2008	103.75	SEP 2017
Lake Letta	Highlands	1981	96.19	95.79	96.95	-0.40	-1.16	0.79	95.00	97.00	100.00	90.27	JUN 2008	100.74	OCT 2017
Lake Lotela	Highlands	1989	103.78	103.46	104.98	-0.32	-1.52	-0.54	104.00	105.00	108.50	0.98	MAY 1995	109.13	SEP 2017
Lake Placid	Highlands	1984	90.82	90.62	91.50	-0.20	-0.88	0.62	90.00	91.50	94.50	88.08	JUN 2008	94.24	SEP 2003
Starr Lake	Polk	1983	104.54	103.82	103.51	-0.72	0.31	-4.18	108.00	110.00	113.00	0.98	OCT 2018	109.80	DEC 2005
Trout Lake	Highlands	1981	94.17	93.82	95.24	-0.35	-1.42	-1.18	95.00	98.00	101.00	87.15	MAY 2001	99.89	SEP 2016


NOTE: M='no data' or 'not determined'

All elevations are referenced to NGVD 1929 datum. Report compiled by Hannah Kolb


HYDROGRAPHS OF REGIONAL LAKES

15-yr Period of Record


Hunters Lake
Northern Lakes




Lake Panasoffkee
Northern Lakes



Camp Lake
Tampa Bay Lakes



Church Lake
Tampa Bay Lakes




— Monthly Mean Elevation - - - Drought Year Low Normal Range


HYDROGRAPHS OF REGIONAL LAKES

15-yr Period of Record


Deer Lake
Tampa Bay Lakes




Gornto Lake
Tampa Bay Lakes



King Lake
Tampa Bay Lakes



Turkey Ford Lake
Tampa Bay Lakes




— Monthly Mean Elevation - - - Drought Year Low Normal Range


HYDROGRAPHS OF REGIONAL LAKES

15-yr Period of Record


Lake Wimauma
Tampa Bay Lakes




Lake Arietta
Polk Uplands Lakes



Lake Buffum
Polk Uplands Lakes



Lake Hamilton
Polk Uplands Lakes




— Monthly Mean Elevation - - - Drought Year Low Normal Range


HYDROGRAPHS OF REGIONAL LAKES

15-yr Period of Record


Lake Otis
Polk Uplands Lakes




Crooked Lake
Lake Wales Ridge Lakes



Lake Jackson
Lake Wales Ridge Lakes



Lake Letta
Lake Wales Ridge Lakes



— Monthly Mean Elevation - - - Drought Year Low Normal Range

Streams

The District processes streamflow data collected by the U.S. Geological Survey (USGS) under a cooperatively funded program between the District and the USGS. Streamflow is recorded daily as water elevations at 12 gauging stations in three regions of the District (see index map in the Appendix). The USGS uses rating curves developed from water level elevations to calculate streamflow discharge in units of cubic feet per second (cfs). For this report, the reported streamflow values are the means of the daily discharge volumes for the current month. The period-of-record high and low values correspond to monthly means and not to peak events. Percentile values are calculated from the monthly means for the period of record, for each station. The percentile is the monthly mean statistically ranked on a scale of zero to 100 that indicates the percent of the period-of-record monthly means that are at or above the present monthly mean. The current year's data are provisional and are subject to revision. Revised data are used for all calculations, as they become available.

Hydrographs are produced for each of the stream stations. Current monthly means for each station are compared to respective 25th and 75th percentiles of the period-of-record monthly means.

During May, 7 of the 12 stations monitored for this report had increased streamflow, compared to last month. Total streamflow decreased in the northern region by 76.6 cfs (49.5 mgd), while streamflow increased in the central and southern regions by 6.4 cfs (4.1 mgd) and 120.4 cfs (77.8 mgd), respectively. District-wide, total streamflow increased by an average of 50.2 cfs (32.4 mgd).

In May, 9 of the 12 stations recorded lower streamflow than in May 2019. Streamflow was lower in the northern and central regions by 173.5 cfs (112.1 mgd) and 61.7 cfs (39.9 mgd), respectively, while streamflow increased in the southern region by 14.8 cfs (9.6 mgd). District-wide, total streamflow was lower, on average, by 220.4 cfs (142.4 mgd), than the May 2019 average.


Compared to historical May discharge values, Withlacoochee River streamflow, measured at the Trilby station and the Holder station averaged in the 27th and 30th percentiles, respectively. Streamflow measured at the stations on the Anclote, Pithlachascotee and Hillsborough Rivers averaged in the 68th, 64th and 30th percentiles of respective historical May readings. Streamflow measured at the Alafia River, Little Manatee River and Peace River at Bartow stations averaged in the 32nd, 65th and 59th percentiles of respective historical May readings. Additionally, streamflow measured at the Josephine Creek, Manatee River, Myakka River and Peace River at Arcadia stations averaged in the 88th, 86th, 66th and 37th percentiles of respective historical May readings.

SUMMARY OF STREAM DISCHARGE FROM MAJOR STREAMS (CFS), MAY 2020


	<i>Beginning Year of Record</i>	<i>Mean Discharge MAY 2020</i>	<i>Mean Discharge APR 2020</i>	<i>Mean Discharge MAY 2019</i>	<i>Change from APR 2020</i>	<i>Change from MAY 2019</i>	<i>MAY 2020 Percentile Rank</i>	<i>Period of Record Low</i>	<i>Record Low Date</i>	<i>Period of Record High</i>	<i>Record High Date</i>
<i>NORTHERN COUNTIES</i>											
Withlacoochee R at Trilby	1928	25.8	30.1	27.9	-4.3	-2.1	27%	0.1	JUN2000	8840	JUN1934
Withlacoochee R near Holder	1928	269.5	346.1	443.0	-76.6	-173.5	30%	33.0	MAR2001	8660	APR1960
<i>CENTRAL COUNTIES</i>											
Anclote River near Elfers	1946	5.3	4.2	6.9	1.1	-1.6	68%	0.8	MAY1962	3710	JUL1960
Pithlachascotee R near New	1963	2.1	4.9	3.8	-2.8	-1.7	64%	0.0	MAY2013	2180	JUN2012
Hillsborough R near Zephyrh	1939	69.5	74.3	71.8	-4.8	-2.3	30%	27.0	MAY2001	12300	MAR1960
Alafia River at Lithia	1932	48.0	46.8	95.1	1.2	-47.1	32%	4.1	JUN2000	40800	SEP1933
Little Manatee R near Wima	1939	44.9	32.9	52.3	12.0	-7.4	65%	0.9	DEC1976	11100	SEP1960
Peace River at Bartow	1939	46.5	46.8	48.1	-0.3	-1.6	59%	0.0	MAY2009	4100	SEP1947
<i>SOUTHERN COUNTIES</i>											
Josephine Cr near DeSoto Ci	1946	32.0	10.2	11.9	21.8	20.1	88%	0.5	MAY1956	1680	SEP1948
Manatee River near Myakka H	1966	43.9	16.1	20.9	27.8	23.0	86%	0.1	MAY1975	6440	JUN2003
Myakka River near Sarasota	1936	29.2	10.9	23.2	18.3	6.0	66%	0.0	JUN2012	10800	JUN2003
Peace River at Arcadia	1931	152.4	99.9	186.7	52.5	-34.3	37%	5.6	MAY2000	34700	SEP1933

HYDROGRAPHS OF MAJOR STREAMS JANUARY 2016 TO MAY 2020


Withlacoochee R at Trilby
Northern Counties




Withlacoochee R near Holder
Northern Counties



Anclole River near Elfers
Central Counties



Pithlachascotee R near New
Central Counties




— Monthly Mean Discharge

- - - POR Monthly Low


■ Normal Range

HYDROGRAPHS OF MAJOR STREAMS JANUARY 2016 TO MAY 2020


Hillsborough R near Zephyrh
Central Counties




Alafia River at Lithia
Central Counties



Little Manatee R near Wima
Central Counties



Peace River at Bartow
Central Counties




— Monthly Mean Discharge

- - - POR Monthly Low


Normal Range

HYDROGRAPHS OF MAJOR STREAMS JANUARY 2016 TO MAY 2020


Josephine Cr near DeSoto Ci
Southern Counties




Manatee River near Myakka H
Southern Counties



Myakka River near Sarasota
Southern Counties



Peace River at Arcadia
Southern Counties



— Monthly Mean Discharge

- - - POR Monthly Low

Normal Range

Springs

The District processes springflow data collected by Tampa Bay Water through a mutual agreement and by the U.S. Geological Survey (USGS) under a cooperatively funded program between the District and the USGS. Springflow is monitored at six gauging stations in two regions of the District (see index map in the Appendix). Springflow data for Rainbow, Silver and Sulphur Springs are recorded as daily water levels. The USGS uses rating curves developed for these springs from historical water level elevations to calculate springflow discharge in units of cubic feet per second (cfs). Weeki Wachee Springs discharge (cfs) is provided as an instantaneous reading calculated by the USGS. Buckhorn and Lithia Springs discharge is obtained from Tampa Bay Water biweekly and weekly, respectively. Period-of-record high and low values correspond to monthly theoretical means and not to peak events. Values are reported as percentiles calculated from an analysis of historical monthly means recorded during a given month. The percentile is the monthly mean ranked on a scale of zero to 100 that indicates the percent of period-of-record values that are above, equal to or below the median (50th percentile) for the current month. The values reported are provisional and are subject to revision at the end of the water year. Revised USGS springflow data are loaded into the District's WMIS when they become available.

Hydrographs are produced for the seven-springflow stations, and current values are compared to respective 25th and 75th percentiles that are calculated from historical data. The 25th and 75th percentiles are calculated using the SASTM software system for data analysis using period-of-record monthly theoretical means for each springflow station analyzed.

During May, four of the six stations reported decreased springflow, while one reported increased flow, compared to the previous month. Sulphur Springs station reported zero (0) flow for the month. Total springflow decreased in the northern and central regions by 29.5 cfs (19.1 mgd) and 1.1 cfs (0.7 mgd), respectively. District-wide, springflow decreased by 30.6 cfs (19.8 mgd).

In May, total springflow recorded at four of the six stations was below last year's levels, while one station had increased flow. Sulphur Springs station reported zero (0) flow during May 2019. Total springflow for the northern and central regions was lower by 333.5 cfs (215.5 mgd) and 13.2 cfs (8.5 mgd). District-wide, springflow was lower by 346.7 cfs (224.0 mgd), compared to May 2019 rates.

Compared to historical period-of-record values for May, total springflow measured in Rainbow, Silver and Weeki Wachee Springs, in the northern region, was in the 14th, 23rd and 76th percentiles of respective historical readings. Springflow measured in Buckhorn and Lithia Springs in the central region was in the 65th and 65th percentiles, respectively, of historical May readings. Sulphur Springs station reported zero (0) flow during May 2020 and percentile calculation was deemed unnecessary.


SUMMARY OF SPRINGS DISCHARGE FROM MAJOR SPRINGS (CFS), MAY 2020

<i>NORTHERN COUNTIES</i>	<i>MAY 2020 Discharge</i>	<i>APR 2020 Discharge</i>	<i>MAY 2019 Discharge</i>	<i>Change From APR 2020</i>	<i>Change From MAY 2019</i>	<i>MAY 2020 Percentile Rank</i>	<i>Period of Record Low</i>	<i>Record Low Date</i>	<i>Period of Record High</i>	<i>Record High Date</i>
Rainbow Springs	537.3	546.6	697.3	-9.3	-160.0	14%	391.0	MAY2012	1060.0	SEP1988
Silver Springs	638.7	656.0	809.4	-17.3	-170.7	23%	141.0	JUN2012	1290.0	OCT1960
Weeki Wachee Springs	159.0	161.9	161.8	-2.9	-2.8	76%	101.0	JUN1994	257.0	OCT2004
<i>CENTRAL COUNTIES</i>										
Sulphur Springs	0.0	0.0	0.0	0.0	0.0	7%	0.0	JUN1994	145.0	MAR1960
Buckhorn Springs	11.1	9.9	11.6	1.2	-0.5	65%	2.2	MAY2006	32.7	AUG2004
Lithia Springs	33.0	35.3	45.7	-2.3	-12.7	65%	6.2	OCT2012	91.5	NOV2004


HYDROGRAPHS OF REGIONAL SPRINGS

JANUARY 2016 TO MAY 2020


Buckhorn Main Spring
Central Counties




Rainbow River at Dunnellon
Northern Counties



Silver River nr Ocala
Northern Counties




Sulphur Springs (Pool) at Sulphur Springs
Central Counties




— Monthly Discharge - - - - - POR Monthly Low Normal Range

HYDROGRAPHS OF REGIONAL SPRINGS JANUARY 2016 TO MAY 2020

Weeki Wachee River nr Brooksville
Northern Counties



Lithia Springs
Central Counties



— Monthly Discharge

- - - POR Monthly Low

Normal Range

GROUND WATER

The ground-water section of this report provides ground-water level information within the District based on geographically delineated areas (regions) within the District. For this report, the District has been divided into three geographical regions that are defined by county boundaries (see index maps in the Appendix). Each regional area includes all or part of each county that is located within that region and that is also within the District's jurisdictional boundaries. The northern region includes the counties of Citrus, Hernando, Lake, Levy, Marion and Sumter, where the Floridan aquifer is generally unconfined and at or near land surface, allowing rainfall to easily recharge (replenish) the aquifer system. The central region includes the counties of Hillsborough, Pasco, Pinellas and Polk, where the Floridan aquifer can be unconfined, semi-confined or confined (overlain by thick clays). Where the Floridan aquifer is confined, recharge to the aquifer from rainfall is low. The southern region includes the counties of Charlotte, DeSoto, Hardee, Highlands, Manatee and Sarasota, where the Floridan aquifer is confined.

Twelve surficial aquifer (shallow, non-artesian) monitor wells and 82 intermediate and Floridan aquifer (deep) monitor wells are measured for this report to determine the relative health of ground-water levels District-wide. Only monitor wells with an adequate and reliable period-of-record water level measurements were selected for the network. For each well, the 25th and 75th percentiles ("low normal" and "high normal," respectively) were calculated for each week of the year using the period-of-record data. The 25th and 75th percentiles are used to represent the lower and upper limits of the normal range, as they are considered a reliable and robust measure of the normal range, and are less affected by extremes in the data record. The end-of month water-level readings measured for this report are compared to their corresponding normal ranges. Trend data from 16 intermediate and Floridan aquifer wells are shown in hydrographs to compare current water levels to the low normal and high normal levels.

Data from these wells are further compiled into regional statistics for the three regions of the District. Wells in the northern counties are unconfined and non-artesian, while those in the southern counties are confined and artesian. Wells included in the central counties vary between confined and unconfined conditions due to the transitional nature of geology in this area. The potentiometric levels of representative Floridan aquifer wells are used to produce the potentiometric surface maps presented in this report.

Surficial Aquifer

In May, monthly analysis indicates that 8 of the 12 surficial aquifer wells recorded water level decreases, compared to last month. Regionally, average surficial aquifer water levels decreased in the northern, central and southern counties by 0.55, 0.10 and 0.17 foot, respectively. District-wide, average surficial aquifer water levels decreased by 0.19 foot.

During May, annual analysis indicates average water levels in 8 of the 12 surficial aquifer wells were lower than May 2019 levels. Average surficial aquifer water levels in the northern counties were higher by 0.22 foot, while levels in the central and southern counties were lower by 0.65 and 0.84 foot, respectively, compared to last year's levels. District-wide, average water levels in surficial wells were lower by 0.55 foot, compared to May 2019 levels.

For May, water levels were above the base of the low normal level in 11 of the 12 surficial wells. Average surficial aquifer water levels in the northern, central and southern counties were 1.76 feet, 1.04 feet and 0.20 foot, respectively, above the base of the low normal level. District-wide, the average water level in surficial wells was 0.95 foot above the base of the low normal level.

SUMMARY OF SURFICIAL AQUIFER LEVELS IN REPRESENTATIVE WELLS, MAY 2020

	MAY 2020 Elev	APR 2020 Elev	MAY 2019 Elev	Change From APR 2020	Change From MAY 2019	MAY Historical Low Normal	MAY Historical High Normal	Departure From Low Normal	Period of Record Low	Record Low Date	Period of Record High	Record High Date
<i>NORTHERN COUNTIES</i>												
Green Swamp	90.28	90.87	89.00	-0.59	1.28	87.36	90.50	2.92	82.95	MAY2000	92.90	SEP2004
Lecanto 2	7.47	7.97	8.32	-0.50	-0.85	6.88	8.42	0.59	5.76	MAY2001	13.04	AUG2003
<i>CENTRAL COUNTIES</i>												
Loughman	90.39	90.64	90.71	-0.25	-0.32	90.15	91.58	0.24	88.40	JUN2001	96.31	SEP2017
Lutz-Lake Fern	56.82	56.59	56.76	0.22	0.05	55.36	56.83	1.46	52.64	NOV2009	60.81	OCT1983
ROMP 50 Shallow	41.82	41.44	41.59	0.38	0.23	40.78	41.53	1.04	38.01	OCT2010	44.05	SEP2001
SR 33 & Combee Road	135.63	135.73	135.65	-0.10	-0.02	132.62	134.06	3.01	129.16	FEB2001	136.81	AUG1995
SR 577 Shallow	118.32	119.18	121.22	-0.86	-2.90	118.22	123.25	0.10	109.99	JAN2000	129.26	SEP2013
Tarpon Road Shallow	10.87	10.76	11.40	0.11	-0.54	10.44	12.05	0.43	9.22	MAY2017	17.25	AUG2015
USGS P-48	99.46	99.66	100.51	-0.20	-1.05	98.45	100.30	1.01	96.07	JUN2001	105.84	SEP2017
<i>SOUTHERN COUNTIES</i>												
Edgeville 4 Shallow	66.42	67.22	66.28	-0.80	0.14	66.02	67.59	0.40	63.76	MAY2012	69.85	JUL2018
ROMP 26 Shallow	67.85	67.38	69.00	0.47	-1.15	67.23	69.55	0.62	64.32	JUN1999	75.30	SEP2017
SR 74	13.80	13.97	15.30	-0.17	-1.50	14.22	15.68	-0.42	12.66	MAY2000	18.78	AUG2013

Intermediate and Floridan Aquifers

In May, monthly analysis indicates that 42 of the 82 intermediate and Floridan aquifer wells monitored for this report recorded water level increases, compared to last month. Regionally, average water levels decreased in the northern counties by 0.73 foot, while levels in the central and southern counties increased by 0.18 foot and 2.09 feet, respectively. District-wide, the average water level in the intermediate and Floridan aquifer increased by 0.66 foot.

During May, annual analysis indicates that 43 of the 82 intermediate and Floridan aquifer wells monitored for this report recorded water level decreases, compared to levels measured in May 2019. Regionally, the mean water level in the northern and central counties was lower by 1.38 feet and 0.20 foot, respectively, while levels increased in the southern counties by 2.36 feet, compared to last year's levels. District-wide, average water levels in intermediate and Floridan aquifer wells were 0.45 feet higher than May 2019 levels.

For May, 81 of the 82 intermediate and Floridan aquifer wells had levels above the base of the low normal level, compared to historical monthly levels. Average water levels in the northern, central and southern counties were 1.58, 6.21 and 7.93 feet, respectively, above the base of the low normal level. District-wide, the average water level in intermediate and Floridan aquifer wells was 5.71 feet above the base of the low normal level.

Record High Monthly Water Level

A record high water level for the historic May record were set in the following wells located in the District's southern counties:

- ROMP 19 West UFA Swnn
- ROMP 19X UFA (SWNN)
- ROMP TR 5-2 UFA (SWNN)

SUMMARY OF INTERMEDIATE AND FLORIDAN AQUIFER LEVELS IN REPRESENTATIVE WELLS, MAY 2020

Regional Summary:

<i>Region</i>	<i>MAY 2020 Mean Elevation</i>	<i>MAY 2020 Relation to POR Median</i>	<i>MAY 2020 Relation to 25th Percentile</i>	<i>MAY 2020 Mean Percentile Rank</i>	<i>APR 2020 Mean Percentile Rank</i>	<i>MAY 2019 Mean Percentile Rank</i>
Northern Counties	37.16	0.04	1.40	51%	59%	71%
Central Counties	56.28	1.95	5.15	67%	64%	71%
Southern Counties	31.24	4.87	8.14	84%	59%	62%

Regional Wells Summary:

<i>NORTHERN COUNTIES</i>	<i>MAY 2020 Elev</i>	<i>APR 2020 Elev</i>	<i>MAY 2019 Elev</i>	<i>Change From APR 2020</i>	<i>Change From MAY 2019</i>	<i>MAY Historical Low Normal</i>	<i>MAY Historical High Normal</i>	<i>Departure From Low Normal</i>	<i>MAY 2020 Percentile Rank</i>	<i>Period of Record Low</i>	<i>Record Low Date</i>	<i>Period of Record High</i>	<i>Record High Date</i>
CE 14 Dunnellon Deep	38.14	39.01	42.79	-0.87	-4.65	35.60	41.47	2.54	50%	31.94	MAY2012	50.74	MAR1998
Chassahowitzka 1 Deep	5.94	6.39	6.41	-0.45	-0.47	5.42	6.52	0.52	52%	4.70	FEB1990	9.70	SEP2004
Inverness Dot Fldn	28.97	29.79	30.36	-0.82	-1.39	27.35	30.32	1.62	52%	21.70	JUN2001	37.80	OCT1982
Mascotte Deep	98.65	99.57	98.72	-0.92	-0.07	97.91	99.86	0.74	41%	93.94	JUN2000	102.66	SEP1988
North Locanto Deep	3.96	4.31	4.66	-0.35	-0.70	3.84	4.89	0.12	33%	2.94	MAY2001	8.10	OCT1982
ROMP 103 Suwannee/Ocala	39.90	40.56	41.57	-0.66	-1.67	39.93	41.47	-0.03	19%	37.53	JUN2017	46.62	SEP2018
ROMP 107 Ocala/Avon Park	11.74	12.26	12.85	-0.52	-1.11	10.73	13.05	1.01	45%	8.08	AUG2007	19.78	NOV1982
ROMP 111 Ocala/Avon Park	48.68	49.09	48.75	-0.41	-0.07	47.45	49.85	1.23	55%	44.22	JUL1992	53.33	SEP2004
ROMP 116 Avon Park	31.95	32.21	32.66	-0.26	-0.71	30.81	33.03	1.14	46%	29.24	MAY2012	39.28	OCT2004
ROMP 119 Avon Park	43.25	43.82	45.94	-0.57	-2.69	41.83	45.26	1.42	48%	39.86	MAY2012	50.98	OCT2004
ROMP 120 Avon Park	43.28	43.94	46.45	-0.66	-3.17	41.16	45.07	2.12	53%	38.71	MAY2012	52.24	MAR1998
ROMP 134 Ocala/Avon Park	48.63	49.66	52.51	-1.03	-3.88	43.04	47.96	5.59	79%	37.80	JUN2012	57.35	APR1998
ROMP 89 Ocala	88.44	90.17	89.16	-1.73	-0.72	87.00	90.87	1.44	35%	82.46	JUN2000	94.93	DEC1997
ROMP 97 Avon Park	18.19	19.02	18.32	-0.83	-0.13	13.54	18.72	4.65	77%	11.34	JUN2002	26.24	SEP2004
ROMP TR 124 Avon Park	2.84	3.45	3.14	-0.61	-0.30	2.28	3.07	0.56	48%	0.77	SEP2004	7.95	JUN1995
ROMP TR 21-2 Ocala/Avpk	2.87	3.28	3.22	-0.41	-0.35	2.60	2.99	0.27	50%	0.40	MAR1991	6.12	OCT1995
Sumter 13 JC 59 Up Fldn	39.32	40.35	41.41	-1.03	-2.09	38.66	42.17	0.66	40%	36.52	MAY2012	47.01	JUN2003
Tidewater 1 FLDN	53.66	54.57	55.85	-0.91	-2.19	52.52	55.81	1.14	41%	48.05	JUN2012	61.81	SEP1982
Webster City Fldn	81.78	82.74	81.66	-0.96	0.12	79.43	82.72	2.35	79%	74.16	MAY2012	88.77	SEP2005
Weeki Wachee Deep Repl	15.11	15.77	15.56	-0.66	-0.46	12.57	16.51	2.54	59%	9.57	MAY2009	22.81	AUG1984

All elevations are referenced to NGVD 1929 datum

Regional Wells Summary (continued):

	MAY 2020 Elev	APR 2020 Elev	MAY 2019 Elev	Change From APR 2020	Change From MAY 2019	MAY Historical Low Normal	MAY Historical High Normal	Departure From Low Normal	MAY 2020 Percentile Rank	Period of Record Low	Record Low Date	Period of Record High	Record High Date
CENTRAL COUNTIES													
Bexley 2 Fldn	60.72	61.55	60.32	-0.83	0.40	58.53	61.00	2.19	72%	56.08	JUN2000	64.50	SEP2017
Coley Deep	83.13	81.49	78.91	1.64	4.22	71.84	83.54	11.29	94%	60.68	JUN2000	90.99	OCT2004
Debuel Road Deep	52.19	53.07	54.43	-0.88	-2.24	51.80	54.77	0.39	34%	46.48	APR2002	60.13	SEP1979
Hills State Park Deep	37.34	38.00	37.49	-0.66	-0.15	36.30	37.92	1.04	42%	35.35	JUN2000	47.42	DEC1997
Lk Alftred Deep	128.03	127.85	127.14	0.18	0.89	124.28	127.25	3.75	92%	119.85	MAY1974	131.18	MAR1998
Loughman Deep	89.44	88.83	88.46	0.61	0.98	88.39	90.87	1.05	44%	85.90	MAY2001	93.23	OCT1979
Lykes Pasco Fldn	66.07	66.66	66.80	-0.59	-0.73	62.03	66.04	4.04	67%	56.94	JUN2000	75.78	OCT2004
Masaryktown Deep	33.34	34.24	36.06	-0.90	-2.72	25.19	36.01	8.15	74%	21.89	AUG1994	50.09	OCT1982
Moon Lake Deep	30.54	30.96	30.98	-0.42	-0.44	29.12	30.61	1.42	50%	26.15	JUN2000	34.89	AUG2015
Pasco 13 nr Drexel Fldn	70.41	70.91	70.77	-0.50	-0.36	70.05	72.61	0.36	31%	68.00	JUN2001	77.14	JUL1960
Pinellas 665 Fldn	9.06	9.26	8.94	-0.20	0.12	8.12	9.69	0.94	73%	6.70	MAY2006	14.79	SEP1959
ROMP 123 Hawthorn/Ocala	10.31	3.42	3.31	6.89	7.00	-11.10	3.57	21.41	97%	-29.47	MAY2000	33.56	FEB1998
ROMP 40 Swnn/AvPk	35.82	31.39	36.37	4.43	-0.55	16.65	31.03	19.17	83%	-4.15	JUN2000	57.37	FEB1998
ROMP 45 Avon Park	68.89	67.71	70.60	1.18	-1.71	54.80	60.82	14.09	87%	33.90	JUN2000	84.44	OCT2004
ROMP 48 Tampa/Suwannee	30.42	26.69	30.80	3.73	-0.38	11.27	27.15	19.15	84%	-7.87	MAY2000	52.64	FEB1998
ROMP 50 Avon Park	3.98	3.76	4.84	0.22	-0.86	-6.56	1.84	10.54	94%	-17.42	FEB2018	14.95	AUG1982
ROMP 58 Ocala	102.60	101.35	100.51	1.25	2.09	95.91	99.63	6.69	81%	89.38	JAN2010	111.01	DEC2005
ROMP 59 Swnn/AvPk	69.52	68.67	71.82	0.85	-2.30	51.80	61.71	17.72	90%	33.33	MAY1981	85.92	OCT2004
ROMP 60 Ocala/Avon Park	68.21	67.48	71.56	0.73	-3.35	60.15	62.39	8.06	67%	51.29	MAY2012	83.25	SEP2018
ROMP 66 Tampa	16.19	16.00	16.89	0.19	-0.70	15.45	17.53	0.74	47%	13.02	JUN2000	25.47	AUG2015
ROMP 76 U Fldn	128.25	128.60	128.13	-0.35	0.12	124.84	127.73	3.41	78%	121.88	JAN2010	132.92	SEP2004
ROMP 87 Avon Park	99.59	101.31	101.17	-1.72	-1.58	98.08	101.31	1.51	44%	94.90	JUN2000	106.30	FEB1998
ROMP 88 Avon Park	101.26	102.89	102.31	-1.63	-1.05	99.61	103.11	1.65	46%	97.42	JUN2000	107.21	SEP2017
ROMP 93 Swnn/AvPk	70.93	72.36	71.87	-1.43	-0.94	64.55	71.83	6.38	73%	59.03	JUN2001	76.56	AUG2018
ROMP DV-1 Suwannee	52.31	53.29	52.59	-0.98	-0.28	45.84	53.14	6.47	65%	12.06	JAN2010	65.72	FEB1998
ROMP TR 10-2 Tampa	9.25	9.13	9.09	0.12	0.16	7.80	8.84	1.45	77%	6.25	MAY2000	14.00	SEP2004
ROMP TR 13-3 Avon Park	14.27	14.77	14.44	-0.50	-0.17	13.70	15.42	0.57	47%	10.16	JUL1987	18.79	AUG2015
SR 52 And CR581 Deep	71.30	72.67	71.48	-1.37	-0.18	65.15	73.06	6.15	62%	56.96	JUN2001	79.44	AUG1965
SR 52 Deep W nr Fivay Jct	52.62	52.72	52.30	-0.10	0.32	50.61	52.55	2.01	78%	48.08	JUN2000	59.53	AUG2010
SR 577 Deep	87.06	88.08	88.59	-1.02	-1.53	81.57	89.78	5.49	58%	72.76	JUN2000	98.51	MAR1998
Sanlon Ranch Fldn	92.00	93.30	95.81	-1.30	-3.81	80.62	89.61	11.38	80%	66.38	MAY1975	105.27	OCT2004
Tarpon Rd Deep	8.83	9.70	8.75	-0.87	0.08	8.72	10.01	0.11	32%	7.50	JUN2006	13.48	AUG2015

All elevations are referenced to NGVD 1929 datum


Regional Wells Summary (continued):

	MAY 2020 Elev	APR 2020 Elev	MAY 2019 Elev	Change From APR 2020	Change From MAY 2019	MAY Historical Low Normal	MAY Historical High Normal	Departure From Low Normal	MAY 2020 Percentile Rank	Period of Record Low	Record Low Date	Period of Record High	Record High Date
SOUTHERN COUNTIES													
Big Slough Deep	31.29	30.40	31.53	0.89	-0.24	29.56	32.07	1.73	59%	26.85	MAY2006	36.12	OCT1995
Cargill FA-1 Fldn	66.85	65.40	68.39	1.45	-1.54	50.55	59.58	16.30	83%	30.50	MAY1981	82.95	OCT2004
Edgeville 3 Deep	24.74	19.40	21.04	5.34	3.70	14.39	26.03	10.35	81%	1.13	MAY2000	41.26	OCT1979
Englewood 14 Deep	4.15	3.80	4.00	0.35	0.15	2.89	3.92	1.26	66%	-0.97	FEB2001	10.51	SEP2003
Florida Pwr @ Piney Point	15.62	14.70	14.12	0.92	1.50	4.50	11.92	11.12	98%	-4.84	MAY1989	21.68	AUG2019
Kibler Deep	5.81	0.20	-3.67	5.61	9.48	-12.38	2.50	18.19	88%	-29.95	MAY2000	29.30	AUG1978
Manasota 14 Deep	17.84	17.60	17.23	0.24	0.61	17.62	20.47	0.22	33%	15.46	MAY2017	22.70	NOV1971
Marshall Deep	38.87	35.10	36.39	3.77	2.48	30.09	40.11	8.78	75%	8.96	JUN2000	55.24	MAR1964
ROMP 16 Ocala	46.75	44.70	42.72	2.05	4.03	42.53	46.46	4.22	85%	28.94	JAN2001	51.21	SEP1995
ROMP 17 Up Fldn	44.64	42.80	42.00	1.84	2.64	40.13	44.05	4.51	84%	31.89	JUN2000	51.64	OCT1994
ROMP 19 West UFA Swnn	27.60	25.70	24.99	1.90	2.61	19.21	25.84	8.39	100%	10.99	JUN2000	33.80	SEP2017
ROMP 19X UFA (SWNN)	32.46	30.30	30.41	2.16	2.05	23.95	30.94	8.51	100%	19.28	JUN2000	39.92	OCT1994
ROMP 20 UFA (SWNN)	21.67	20.50	18.32	1.17	3.35	15.16	19.29	6.51	97%	11.99	MAY2007	26.66	SEP2017
ROMP 22 UFA (SWNN)	15.94	12.40	11.84	3.54	4.10	3.68	13.01	12.26	99%	-3.71	MAY2000	30.18	FEB1998
ROMP 26 Swnn/AvPk	43.48	40.60	38.91	2.88	4.57	35.77	43.26	7.71	80%	19.48	JAN2010	51.28	OCT1979
ROMP 28X Swnn/AvPk	69.98	68.10	66.92	1.88	3.06	64.49	68.14	5.49	96%	57.24	JAN2010	74.68	OCT1995
ROMP 30 Swnn/AvPk	39.86	36.90	38.58	2.96	1.28	26.07	39.01	13.79	75%	-0.20	JUN2000	60.52	MAR1998
ROMP 31 Swnn/AvPk	36.49	31.80	35.02	4.69	1.47	20.12	35.15	16.37	81%	-6.22	JUN2000	57.92	MAR1998
ROMP 32 Low Ocala/Avpk	21.60	15.60	18.62	6.00	2.98	1.84	18.88	19.76	90%	-17.74	JUN2000	44.73	FEB1998
ROMP 43XX Avon Park	87.48	86.50	84.48	0.98	3.00	80.97	85.85	6.51	86%	70.93	JAN2010	93.95	SEP2004
ROMP 9 UFA (SWNN)	41.67	40.60	40.93	1.07	0.74	39.03	41.29	2.64	79%	37.00	JAN2001	46.35	SEP2006
ROMP TR 1-2 Up Fldn	44.89	44.20	44.31	0.69	0.58	43.20	44.78	1.69	84%	40.72	JUN2000	47.22	SEP2015
ROMP TR 3-1 Up Fldn	33.91	33.30	33.25	0.61	0.66	31.86	33.30	2.05	92%	29.04	JUN2000	35.98	SEP2017
ROMP TR 5-1 Suwannee	18.95	18.30	17.20	0.65	1.75	15.40	18.46	3.55	91%	13.26	JUN2000	22.56	SEP2017
ROMP TR 5-2 UFA (SWNN)	25.01	23.40	22.21	1.61	2.80	17.47	23.18	7.54	100%	13.75	MAY2006	31.10	OCT1994
ROMP TR 7-1 Tampa	18.59	18.50	17.42	0.09	1.17	12.98	16.72	5.61	95%	10.01	JUN2000	24.23	SEP2017
ROMP TR 7-4 Swnn/Ocala	11.86	10.90	9.38	0.96	2.48	2.83	10.62	9.03	82%	-3.55	MAY2000	24.35	AUG2019
Romp TR SA-1 UFS (SWNN)	9.04	9.70	8.58	-0.66	0.46	5.96	10.89	3.08	73%	2.89	MAY2017	22.04	SEP1999
Sarasota Office Up Floridan	12.80	10.70	10.42	2.10	2.38	4.07	21.73	8.73	72%	-4.25	JUN2000	34.20	MAR1931
Verna T 0-1	11.43	6.40	4.87	5.03	6.56	-0.62	10.09	12.05	83%	-15.73	MAY2000	33.32	JAN1984


All elevations are referenced to NGVD 1929 datum

HYDROGRAPHS OF REPRESENTATIVE INTERMEDIATE AND FLORIDAN AQUIFER WELLS JANUARY 2017 TO MAY 2020


Chassahowitzka #1
Northern Region




Mascotte Deep
Northern Region



ROMP 107 Ocala/Avon Park
Northern Region




Sumter 13 Upper Fldn
Northern Region




— Average Weekly Elevation - - - - - POR Weekly Low Normal Range

HYDROGRAPHS OF REPRESENTATIVE INTERMEDIATE AND FLORIDAN AQUIFER WELLS JANUARY 2017 TO MAY 2020


Weeki Wachee Deep
Northern Region




Bexley Well 2
Central Region



Hillsborough St Park Deep
Central Region




Pinellas 665
Central Region




— Average Weekly Elevation - - - - - POR Weekly Low Normal Range

HYDROGRAPHS OF REPRESENTATIVE INTERMEDIATE AND FLORIDAN AQUIFER WELLS JANUARY 2017 TO MAY 2020


SR 52 Deep (West) near Fivay
Central Region




Edgeville 3 Deep
Southern Region



Kibler Deep
Southern Region



Manasota 14 Deep
Southern Region




— Average Weekly Elevation

- - - POR Weekly Low


Normal Range

HYDROGRAPHS OF REPRESENTATIVE INTERMEDIATE AND FLORIDAN AQUIFER WELLS JANUARY 2017 TO MAY 2020


Marshall Deep
Southern Region




ROMP 26 Suwannee/Avon Park
Southern Region



ROMP TR 5-1 Suwannee
Southern Region



Romp TR SA-1
Southern Region




— Average Weekly Elevation

- - - POR Weekly Low


Normal Range

Generalized Potentiometric Surface of the Floridan Aquifer May 2020



Compiled by M.L. Crowell


Generalized Change
in the Potentiometric Surface
of the Floridan Aquifer
April 2020 - May 2020



Compiled by M.L. Crowell

Contour interval = 2 feet

Generalized Change in the Potentiometric Surface of the Floridan Aquifer May 2019 - May 2020



Compiled by M.L. Crowell

Contour interval = 3 feet

Public Supply Wellfields

Water levels are measured in 21 monitor wells (9 surficial, 12 intermediate and Floridan aquifer wells) located at nine public supply wellfields in the District. Thirteen of the 21 monitor wells have water levels measured monthly, two biweekly, and six weekly. Monthly data are tabulated to compare recent water levels to historical means.

In May, monthly analysis indicates that average water levels decreased in 8 of the 12 intermediate and Floridan wells and 5 of the 9 surficial wells, compared to the previous month. Average water levels measured in the intermediate and Floridan wells decreased 0.41 foot, while levels measured in surficial wells decreased 0.11 foot.

During May, annual analysis indicates average water levels increased in 8 of the 12 intermediate and Floridan wells, while levels decreased in 6 of the 9 surficial wells, compared to last year's levels. Water levels measured in the intermediate and Floridan wells averaged 0.60 foot above last year's levels, while surficial water levels averaged 0.04 foot below May 2019 levels.

For May, average water levels in all 12 intermediate and Floridan wells and all 9 surficial wells were above the base of their respective normal level, compared to the historical monthly levels. Water levels measured in the intermediate and Floridan wells averaged 9.94 feet above the base of the normal level, while levels in the surficial wells averaged 5.02 feet above the base of the normal level.

SUMMARY OF GROUNDWATER LEVELS IN REPRESENTATIVE WELLFIELD WELLS, MAY 2020

	MAY 2020 Elev	APR 2020 Elev	MAY 2019 Elev	Change From APR 2020	Change From MAY 2019	MAY Historical Low Normal	MAY Historical High Normal	Departure From Low Normal	Period of Record Low	Record Low Date	Period of Record High	Record High Date
<i>INT/FLORIDAN WELLS</i>												
Cosme-Odessa Cosme No. 3	22.58	22.76	24.01	-0.18	-1.43	19.61	24.69	2.97	11.58	JUN2000	33.84	AUG2012
Cross Bar WRW	49.46	50.23	51.86	-0.77	-2.40	41.06	50.65	8.40	33.88	DEC1993	61.37	AUG1984
Cypress Crk TMR-1 Deep	61.63	62.29	60.83	-0.66	0.80	47.54	59.03	14.09	36.93	FEB2001	69.29	AUG2003
Cypress Crk TMR-3 Deep	60.44	61.14	60.06	-0.71	0.37	45.73	56.95	14.71	34.22	FEB2001	67.18	SEP2004
Eldridge-Wilde 11 Deep	21.19	21.85	19.19	-0.66	2.00	7.87	18.57	13.32	0.31	SEP1990	27.69	SEP2013
Eldridge-Wilde 2S	19.64	18.32	19.56	1.32	0.09	6.86	18.13	12.78	-1.05	JUN2000	25.44	SEP2013
Morris Bridge 3A Deep	28.23	28.00	26.61	0.23	1.62	23.02	28.65	5.21	17.02	MAY2009	35.84	FEB1998
Section 21 Hills 13 Deep	37.57	41.93	41.91	-4.37	-4.34	32.14	38.50	5.43	21.54	JUN2002	49.60	AUG2012
South Pasco 42	53.23	53.89	47.66	-0.66	5.57	38.53	47.04	14.70	27.98	MAY2002	58.65	SEP2017
South Pasco SR 54 Deep	54.52	54.96	51.03	-0.44	3.49	42.08	49.72	12.44	33.49	MAY2002	59.26	AUG2012
Starkey Regional	34.08	33.45	34.36	0.63	-0.28	28.28	33.01	5.80	25.03	JUN2000	38.37	AUG2015
Verna 08	4.22	2.84	2.57	1.38	1.65	-5.26	5.90	9.48	-24.32	MAY1989	26.68	FEB1998
<i>SURFICIAL WELLS</i>												
Cosme-Odessa IC-6	36.38	36.00	36.41	0.39	-0.03	35.29	37.02	1.09	33.03	MAR1991	42.95	AUG2015
Cross Bar SERW	69.23	69.32	68.23	-0.10	1.00	67.50	69.57	1.73	59.80	SEP2007	71.41	AUG2018
Cypress Crk TMR-1 Shallow	61.73	62.26	60.97	-0.53	0.76	54.32	62.00	7.41	39.89	DEC2000	69.24	AUG2018
Cypress Crk TMR-3 Shallow	58.76	58.55	58.80	0.21	-0.04	53.76	58.57	5.00	52.68	MAY1997	64.80	JUN2003
Eldridge-Wilde 11 Shallow	25.94	25.85	26.90	0.09	-0.96	15.05	24.47	10.89	10.77	JUN1994	31.72	JUL2015
Morris Bridge 3A Shallow	32.34	31.93	31.58	0.42	0.76	28.51	33.79	3.83	24.86	MAY2009	39.03	DEC1997
Section 21 Hills 13 Shallow	49.33	50.67	50.43	-1.34	-1.10	40.78	50.23	8.55	33.81	MAY2001	53.82	AUG2012
South Pasco SR 54 Shallow	58.13	58.21	58.43	-0.08	-0.30	56.17	58.24	1.96	54.43	OCT1980	60.49	SEP1998
Starkey 707	29.83	29.87	30.28	-0.04	-0.45	25.13	29.58	4.70	22.70	JUN2000	34.18	AUG2015

Aquifer Resource Index

Aquifers are underground layers of rock and sand that hold water. In southwest Florida, more than 80 percent of the water supply comes from aquifers. The Aquifer Resource Index (ARI) was created to provide information to the media, residents, local governments and other interested parties about current ground-water conditions and how they compare to historical records. The underlying purpose of this index is to provide the public with a gauge of ground-water conditions in their area, so they can develop an understanding of the severity and cycles of drought and recovery

This ARI report has been modified to now reflect percentile values to compare current aquifer levels to historical levels during the same time of year on a scale of 0-100. For example, if the regional groundwater level is at the 50th percentile, it means that half of the historical levels for this time of year were higher and half were lower than the current level.


To determine the ARI percentile value for each geographic region (indicated below), the percentile values of the monitor wells located within that region are averaged. Monitor wells with an adequate and reliable period-of-record to calculate weekly percentiles were selected for the network. There are 20 wells located in the northern region, 32 wells located in the central region and 30 wells located in the southern region, that are currently used for determining the regional percentiles. A total of 82 wells District-wide are used for the ARI Network (see index map in Appendix).

Weekly Aquifer Resource Index Level (Percentile)

Report Date	Northern Region	Central Region	Southern Region
05/03/2020	58	66	67
05/10/2020	56	63	65
05/17/2020	51	61	67
05/24/2020	53	64	75
05/31/2020	51	67	84

Note: Any regional percentile value that falls on or between the 25th and 75th percentile is considered “normal.” Less than the 25th would be considered “below-normal,” while above the 75th would be considered “above-normal.”

AQUIFER RESOURCE INDEX*
May 2020



*Average Groundwater Level Relative to Low Normal, NGVD 29

Compiled By Steve DeSmith

PUBLIC SUPPLY SURFACE WATER RESERVOIRS

CITY OF TAMPA RESERVOIR (Hillsborough River Basin): Constructed in 1924, it is located on the Hillsborough River in Hillsborough County. It is the fourth largest public supply surface water facility in the District. It is the main water supply for the City of Tampa and has a total storage capacity of 1.7 billion gallons (bg). The total usable volume is 1.4 bg, when the reservoir elevation is 22.5 feet NGVD. It is an in-stream reservoir with a depth that ranges between nine and 22 feet. Given this amount of water, it is estimated that a 15-day supply of water is available from this facility over an extended dry period. During periods of low water due to drought conditions, the facility is permitted to pump water from two alternate sources. The first of these two sources is the Tampa Bypass Canal. Water is pumped over the water control structure at S-161 into the Hillsborough River above the dam. The second source is Sulphur Springs, just downstream from the dam, where water is captured at the spring and pumped back behind the dam. Withdrawals from both sources are in strict accordance with pumpage schedules as outlined in the facility's water use permit. When water levels fall below 12 feet NGVD, water cannot be withdrawn because the reservoir level is below the intake pipes. The permitted average daily withdrawal for this facility is 82 mgd, with a permitted maximum daily withdrawal of 104 mgd. Currently, ground water wells are not used to augment this facility. The minimum producible level is 9.00 feet.

PEACE RIVER RESERVOIRS - PEACE RIVER/MANASOTA REGIONAL WATER

SUPPLY AUTHORITY (Peace River Basin): The Peace River reservoirs are located in southwestern DeSoto County. They are an off-stream reservoir system consisting of two reservoirs that store surface water captured from the Peace River during wet periods. The first reservoir, Reservoir 1, was built in 1980 and encompasses approximately 85 acres, has a water depth of approximately 31 feet, and has a total storage capacity of approximately 625 million gallons. The second reservoir, Reservoir 2, was built in 2009, covers about 616 acres, has a water depth of approximately 35 feet, and has a total storage capacity of about 6.0 billion gallons. The PRMRWSA facility ranks as the third largest in the District for total volume storage and supplies water to Charlotte, DeSoto, Manatee and Sarasota counties and to the City of North Port. The facility also uses an aquifer storage recovery (ASR) system for storing treated water pumped from the river. The minimum producible level at Reservoir 1 is Elevation 8.0 feet, while Reservoir 2 is Elevation 27.0 feet.

MANATEE RESERVOIR (Manasota Basin): Completed in 1967 by the damming of the Manatee River, the Manatee Reservoir is the second largest of the six surface-water public supply facilities within the District. Located in Manatee County, this in-stream facility has a storage capacity of 7.5 bg. The service area of the Manatee reservoir is the unincorporated portions of Manatee County, the City of Palmetto and Anna Maria Island, and also the Sarasota SUD#1. This reservoir provides essentially all public supply for Manatee County, with the exception of the City of Bradenton. The total size of this reservoir is 1800 acres with an average depth of 15 feet. With the reservoir full, the facility has approximately 220 days of available water supply. When the surface-water elevation drops below 21.0 feet, water cannot be withdrawn because levels are below the facility's intakes. The permitted average daily withdrawal for this facility is 34.9 mgd, with a permitted peak monthly quantity of 41.9 mgd. The minimum producible level is 21.00 feet.

EVERS RESERVOIR (Manasota Basin): Constructed in 1935 and expanded in 1985, it is located on the Braden River in Manatee County. This is the fifth largest public supply reservoir in the District. Its main service area is the City of Bradenton and approximately 500 customers outside the city. It has a total storage capacity of 1.5 bg. The total size of the facility is 300 acres with an average depth of 12 feet. Water ceases to flow over the dam when the level falls below 3.84 feet NGVD. During the 1985 drought, while expansion of the facility was taking place, the water level dropped to one foot below sea level and demand was still met. Given a completely full reservoir, with no water going over the spillway, it is estimated the facility could supply water for approximately 260 days, with no input from rainfall. The permitted average daily withdrawal for this facility is 6.95 mgd, with a permitted peak monthly quantity of 8.13 mgd. Currently, ground-water wells are not used to augment this facility.

SHELL CREEK RESERVOIR (Peace River Basin): Shell Creek Reservoir, located in Charlotte County, is the sixth largest surface water system within the District. This system was built in 1964 and services the City of Punta Gorda as well as unincorporated areas surrounding the city limits. The Shell Creek Reservoir is fed by two primary tributaries, Shell Creek from the east and Prairie Creek from the northwest. The total drainage area at Hendrickson Dam is 373 square miles. It has a surface area of 800 acres and depths of 10 to 12 feet. Total storage capacity is 765 mg. Even with this low volume of water, personnel at this facility estimate they have approximately 125 days of available supply with no input from rainfall. Water ceases to flow across the weir when surface elevations drop below 5.0 feet NGVD, and at 3.7 feet NGVD water quality becomes a major concern. When surface elevations drop below 1.75 feet NGVD, the water is below the intakes and withdrawal of water is not possible. The permitted average daily withdrawal by this facility is 5.358 mgd, with a permitted peak monthly quantity of 6.901 mgd. The minimum producible level is 1.70 feet.

C.W. BILL YOUNG REGIONAL RESERVOIR - TAMPA BAY WATER (Alafia River Basin): Constructed in early 2005, it is the largest public supply surface water facility in the District. Located in southern Hillsborough County, it is an off-stream reservoir that stores surface water skimmed from the Tampa Bypass Canal and Alafia and Hillsborough Rivers. It services the Tampa Bay region through the Tampa Bay Water regional public supply water distribution system. The reservoir has an estimated storage capacity of 15.0 bg when the water level elevation is 136.5 feet NGVD. The reservoir is approximately 45 feet deep, two miles long and one mile wide, and encompasses a land area of approximately 1,100 acres. It reportedly has the capacity to provide 25 percent of the Tampa Bay region's public supply needs for six months and can supply the Tampa Bay regional surface water treatment plant at full capacity for 227 days.

Reservoirs

Water-level data for the seven reservoirs are obtained weekly from the USGS, Manatee County Utilities Department, Peace River/Manasota Regional Water Supply Authority, or Tampa Bay Water. The last weekly water-level value of the month is indicated in this report. The values reported are provisional and subject to revision.

In May, five of the seven reservoirs monitored for this report recorded water-level decreases, compared to last month. The Evers, Bill Young, Peace River Nos. 1 and 2, and Shell Creek reservoirs posted water level decreases of 0.18 foot, 6.45 feet, 4.70 and 2.10 feet, and 0.03 foot, respectively, compared to last month. The Hillsborough River and Lake Manatee reservoirs posted water level increases of 0.17 foot and 1.48 feet, respectively, for the month.


SUMMARY OF WATER LEVELS IN WATER SUPPLY RESERVOIRS (ELEVATION IN FEET, NGVD 29)

RESERVOIR	2020 April	2020 May	2019 May	Change from Prior Month	Change from Prior Year
Evers					
City of Bradenton	4.05	3.87	3.64	-0.18	0.23
Hillsborough					
City of Tampa	21.33	21.50	21.11	0.17	0.39
Lake Manatee					
Manatee County	38.06	39.54	39.04	1.48	0.50
C.W. Bill Young Regional					
Tampa Bay Water	122.34	115.89	131.78	-6.45	-15.89
Peace River					
PRMRWSA Reservoir #1	25.10	20.40	24.30	-4.70	-3.90
PRMRWSA Reservoir #2	54.30	52.20	57.30	-2.10	-5.10
Shell Creek					
City of Punta Gorda	5.04	5.01	5.07	-0.03	-0.06


NGVD - National Geodetic Vertical Datum

Reported data are provisional and subject to revision.

EVERS RESERVOIR City of Bradenton




HILLSBOROUGH RESERVOIR City of Tampa




LAKE MANATEE RESERVOIR

Manatee County




C.W. BILL YOUNG REGIONAL RESERVOIR


Tampa Bay Water




PEACE RIVER RESERVOIR No. 1
Peace/Manasota Reg. Water Supply



PEACE RIVER RESERVOIR No. 2
Peace/Manasota Reg. Water Supply



SHELL CREEK RESERVOIR City of Punta Gorda



APPENDICES

Rainfall percentiles by interval and region, inches.

Rainfall Interval	Region	10TH Percentile (P10)	25th Percentile (P25)	50th Percentile (P50)	75th Percentile (P75)	90th Percentile (P90)
Annual total	<i>Northern</i>	43.19	48.35	54.01	58.86	63.46
Annual total	<i>Central</i>	41.45	46.10	52.16	57.28	63.82
Annual total	<i>Southern</i>	42.05	46.25	52.19	57.82	63.43
Annual total	<i>District</i>	43.12	47.22	52.99	57.46	62.83
Dry season total	<i>Northern</i>	15.27	18.42	23.79	28.72	32.10
Dry season total	<i>Central</i>	13.32	16.48	21.59	26.86	30.83
Dry season total	<i>Southern</i>	12.35	15.68	21.24	26.23	30.01
Dry season total	<i>District</i>	13.71	16.79	22.02	27.22	29.70
Wet season total	<i>Northern</i>	22.79	25.44	29.45	33.43	38.16
Wet season total	<i>Central</i>	23.22	25.79	29.71	34.86	39.22
Wet season total	<i>Southern</i>	24.37	27.37	30.58	35.88	41.68
Wet season total	<i>District</i>	23.92	27.16	29.97	34.71	38.93
January total	<i>Northern</i>	0.73	1.50	2.45	4.00	5.30
January total	<i>Central</i>	0.72	1.21	2.23	3.72	4.60
January total	<i>Southern</i>	0.39	0.93	1.88	3.31	4.93
January total	<i>District</i>	0.65	1.17	2.10	3.55	4.90
February total	<i>Northern</i>	0.82	1.42	2.82	4.08	5.76
February total	<i>Central</i>	0.60	1.12	2.38	4.17	5.50
February total	<i>Southern</i>	0.36	1.26	2.21	3.63	4.93
February total	<i>District</i>	0.73	1.32	2.38	3.94	5.12
March total	<i>Northern</i>	1.00	2.06	3.15	5.43	7.21
March total	<i>Central</i>	0.97	1.66	2.96	4.95	6.44
March total	<i>Southern</i>	0.81	1.28	2.56	4.29	6.68
March total	<i>District</i>	1.09	1.64	3.04	4.86	6.92
April total	<i>Northern</i>	0.65	1.33	2.38	3.95	5.52
April total	<i>Central</i>	0.51	0.96	1.87	3.44	5.59
April total	<i>Southern</i>	0.48	1.19	2.04	3.75	4.66
April total	<i>District</i>	0.65	1.20	2.24	3.72	5.12
May total	<i>Northern</i>	1.18	1.95	3.21	4.67	6.92
May total	<i>Central</i>	0.87	1.64	2.73	4.58	5.75
May total	<i>Southern</i>	1.17	1.91	3.36	5.22	6.75
May total	<i>District</i>	1.23	2.04	3.24	4.87	6.29
June total	<i>Northern</i>	4.60	5.47	7.27	8.63	10.16
June total	<i>Central</i>	3.65	4.79	6.46	8.27	9.48
June total	<i>Southern</i>	4.22	5.63	7.44	9.06	12.06
June total	<i>District</i>	4.55	5.46	7.24	8.60	10.99
July total	<i>Northern</i>	5.36	6.75	8.29	9.16	11.52
July total	<i>Central</i>	4.89	5.98	8.35	10.05	11.44
July total	<i>Southern</i>	5.68	6.94	8.11	9.50	10.99
July total	<i>District</i>	5.60	6.83	8.19	9.57	10.58
August total	<i>Northern</i>	5.44	6.30	7.31	9.72	11.33
August total	<i>Central</i>	5.52	6.55	7.90	9.62	12.03
August total	<i>Southern</i>	5.55	6.22	7.70	8.97	10.49
August total	<i>District</i>	5.65	6.52	7.70	9.37	10.67
September total	<i>Northern</i>	2.79	4.18	5.84	8.04	11.35
September total	<i>Central</i>	3.19	5.11	6.46	8.50	11.69
September total	<i>Southern</i>	4.30	5.46	6.94	9.33	11.85
September total	<i>District</i>	3.85	5.21	6.53	8.62	11.65
October total	<i>Northern</i>	0.63	1.27	2.46	4.40	6.15
October total	<i>Central</i>	0.69	1.39	2.61	4.03	6.13
October total	<i>Southern</i>	0.92	1.78	2.73	4.27	6.04
October total	<i>District</i>	1.06	1.57	2.80	4.15	5.79



Rainfall percentiles by interval and region, inches (continued).

Rainfall Interval	Region	10TH Percentile (P10)	25th Percentile (P25)	50th Percentile (P50)	75th Percentile (P75)	90th Percentile (P90)
November total	<i>Northern</i>	0.38	0.71	1.63	2.88	4.56
November total	<i>Central</i>	0.25	0.47	1.42	2.82	4.33
November total	<i>Southern</i>	0.40	0.64	1.46	2.56	3.82
November total	<i>District</i>	0.37	0.63	1.53	2.73	4.39
December total	<i>Northern</i>	0.54	1.06	2.06	3.71	5.19
December total	<i>Central</i>	0.48	0.84	1.89	3.03	4.87
December total	<i>Southern</i>	0.45	0.77	1.56	2.63	4.18
December total	<i>District</i>	0.54	0.89	1.86	2.92	4.34


Rainfall characterization ranges

Characterization	Range	Corresponding Rainfall Percent of Normal (approximate)
Very dry	Less than the P10 rainfall	Less than 80 percent of normal
Drier than normal	P10 to P24 rainfall	80 to 90 percent of normal
Normal	P25 to P75 rainfall	90 to 110 percent of normal
Wetter than normal	P76 to P90 rainfall	110 to 120 percent of normal
Very Wet	Greater than the P90 rainfall	Greater than 120 percent of normal



RADAR
Rainfall
Estimate
Grid
System



Selected Lake Monitoring Stations Northern Region





Selected Lake Monitoring Stations Tampa Bay Region





Selected Lake Monitoring Stations

Polk Uplands Region



Selected Lake Monitoring Stations

Lake Wales Ridge Region



Selected Lake Monitoring Stations

Northern Region

<u>Map ID</u>	<u>Site Name</u>
1	Lake Iola
2	Hancock Lake
3	Lake Pasadena
4	Big Fish Lake
5	Crews Lake
6	Lake Lindsey
7	Moon Lake
8	Hunters Lake
9	Tsala Apopka at Floral City
10	Lake Miona
11	Pana Vista Outlet River
12	Outlet River at Panacoochee
13	Tsala Apopka at Inverness
14	Spring Lake
15	Tsala Apopka at Hernando
16	Little Lake (Consuella)
17	Lake Panasoffkee

Tampa Bay Region

<u>Map ID</u>	<u>Site Name</u>	<u>Map ID</u>	<u>Site Name</u>
18	Mud (Walden) Lake	40	Lake Brooker
19	Gornto Lake	41	Cooper Lake
20	Carlton Lake	42	Lake Thomas
21	Lake Wimauma	43	Brant Lake
22	King Lake near San Antonio	44	Turkey Ford Lake
23	Lake Linda	45	Church Lake
24	Lake Padgett	46	Horse Lake
25	Keene Lake	47	Lake Alice
26	Egypt Lake	48	Lake Calm
27	Long Pond	49	Keystone Lake
28	Lake Stemper	50	Crescent Lake
29	Camp Lake		
30	Lake Ann (Parker)		
31	Lake Hiawatha		
32	Platt Lake		
33	Lake Carroll		
34	Bay Lake		
35	Lake LeClare		
36	Little Lake		
37	Rainbow Lake		
38	Lake Harvey		
39	Deer Lake		

Selected Lake Monitoring Stations


Lake Wales Ridge Region

<u>Map ID</u>	<u>Site Name</u>
51	Trout Lake
52	Lake Letta
53	Lake Jackson at Sebring
54	Crooked Lake near Babson Park
55	Lake Starr
56	Lake Annie
57	Lake Placid
58	Lake Clay
59	Lake Lotela

Polk Uplands Region

<u>Map ID</u>	<u>Site Name</u>
60	Lake Helene
61	Lake Gibson
62	Lake Ariana
63	Lake Arietta
64	Lake Juliana
65	Clearwater Lake
66	Blue Lake South
67	Lake McLeod
68	Eagle Lake
69	Lake Buffum
70	Lake Garfield
71	Lake Howard
72	Lake Bonny
73	Lake Alfred
74	Lake Ruby
75	Lake Hamilton
76	Lake Otis
77	Lake Fannie
78	Lake Conine

Selected Stream Monitoring Stations



Selected Stream Monitoring Stations

<u>Map ID</u>	<u>Site Name</u>
1	Withlacoochee River near Holder
2	Withlacoochee River at Trilby
3	Hillsborough River near Zephyrhills
4	Pithlachascotee River near New Port Richey
5	Anclote River near Elfers
6	Alafia River at Lithia
7	Little Manatee River near Wimauma
8	Josephine Creek near DeSoto City
9	Peace River at Arcadia
10	Peace River at Bartow
11	Myakka River near Sarasota
12	Manatee River near Myakka Head

STREAM MONITORING STATIONS

WITHLACOOCHEE RIVER (Northern Region)

Total length: 157 miles
Headwaters: NW Polk and southern Sumter Counties
Elevation: 135 feet
Tributaries: Little Withlacoochee, Big Gant Canal, Jumper Creek, Shady Brook, Outlet River of Lake Panasoffkee, Leslie Heifner Canal, Orange State Canal, Tsala Apopka Outfall Canal and Rainbow Springs.
Mouth: Gulf of Mexico, Citrus County
Average fall: 0.9 feet/mile
Drainage area: 2000 square miles

Holder Station

County: Marion
Period-of-record: 1928
Location: 38 miles upstream from mouth
Avg daily discharge: 1036.3 cfs
Runoff per year: 10.36 inches
Max of monthly avg discharge: 7096.3 cfs in 04/1960
Min of monthly avg discharge: 111.8 cfs in 07/1992
Drainage area: 1825 square miles

Trilby Station

County: Hernando
Period-of-record: 1928
Location: 93 miles upstream from mouth
Avg daily discharge: 336.3 cfs
Runoff per year: 6.73 inches
Max of monthly avg discharge: 4254.7 cfs in 09/1933
Min of monthly avg discharge: 6.1 cfs in 07/1992
Drainage area: 570 square miles

ANCLOTE RIVER (Central Region)

Total length: 27.5 miles
Headwaters: South-central Pasco County, west of Land O Lakes
Elevation: 65 feet
Tributaries: South Branch and Hollin Creek
Mouth: Gulf of Mexico, Pasco County
Average fall: 2.4 feet/mile
Drainage area: 113 square miles

Elfers Station

County: Pasco
Period-of-record: 1946
Location: 16 miles upstream from mouth
Avg daily discharge: 65.1 cfs
Runoff per year: 12.20 inches
Max of monthly avg discharge: 633.8 cfs in 09/1988
Min of monthly avg discharge: 1.4 cfs in 05/1981
Drainage area: 72.5 square miles

HILLSBOROUGH RIVER (Central Region)

Total length: 55 miles
Headwaters: Southeast Pasco County
Elevation: 77 feet
Tributaries: Crystal Springs, Blackwater Creek, Flint Creek, Trout Creek, Cypress Creek, Curiosity Creek and Sulphur Springs
Mouth: Hillsborough Bay
Average fall: 1.4 feet/mile
Drainage area: 690 square miles

Zephyrhills Station

County: Hillsborough
Period-of-record: 1939
Location: 40 miles upstream from mouth
Avg daily discharge: 244.2 cfs
Runoff per year: 15.05 inches
Max of monthly avg discharge: 2284.5 cfs in 12/1997
Min of monthly avg discharge: 47.1 cfs in 05/1994
Drainage area: 200 square miles

PITHLACHASCOTEE RIVER (Central Region)

Total length: 41 miles
Headwaters: Crews Lake and Masaryktown area in central Pasco and southern Hernando Counties
Elevation: 120 feet
Mouth: Gulf of Mexico
Average fall: 2.9 feet/mile
Drainage area: 191 square miles

New Port Richey Station:

County: Pasco
Period-of-record: 1963
Location: 10.5 miles upstream from mouth
Avg daily discharge: 27.9 cfs
Runoff per year: 2.11 inches
Max of monthly avg discharge: 329.4 cfs in 09/1988
Min of monthly avg discharge: 0.0 cfs
Drainage area: 180 square miles

ALAFIA RIVER (Central Region)

Total length: 24 miles
Headwaters: Western Polk and eastern Hillsborough Counties
Tributaries: North and South Prongs, Lithia Springs, and Buckhorn Creek.
Elevation: 30 feet
Mouth: Tampa Bay
Average fall: 1.5 feet/mile
Drainage area: 420 square miles

Lithia Station:

County: Hillsborough
Period-of-record: 1932
Location: 16 miles upstream from mouth
Avg daily discharge: 339.7 cfs
Runoff per year: 13.59 inches
Max of monthly avg discharge: 4185.4 cfs in 09/1933
Min of monthly avg discharge: 13.0 cfs in 05/1945
Drainage area: 335 square miles

LITTLE MANATEE RIVER (Central Region)

Total length: 39 miles
Headwaters: Southeast Hillsborough County
Tributaries: Carlton Branch, the South Fork, Dug Creek and Cypress Creek.
Elevation: 130 feet
Mouth: Tampa Bay
Average fall: 3.4 feet/mile
Drainage area: 225 square miles

Wimauma Station:

County: Hillsborough
Period-of-record: 1939
Location: 15 miles upstream from mouth
Avg daily discharge: 171.4 cfs
Runoff per year: 15.68 inches
Max of monthly avg discharge: 1443.7 cfs in 07/1945
Min of monthly avg discharge: 3.8 cfs in 05/45
Drainage area: 149 square miles

JOSEPHINE CREEK (Southern Region)

Total length: 12 miles
Headwaters: Lake Josephine in central Highlands County
Elevation: 80 feet
Mouth: Lake Istokpoga in Highlands County
Average fall: 3.5 feet/mile
Drainage area: 143 square miles

DeSoto City Station:

County: Highlands
Period-of-record: 1946
Location: 4.9 miles upstream of mouth
Avg daily discharge: 74.2 cfs
Runoff per year: 8.90 inches
Max of monthly avg discharge: 769.9 cfs in 09/1960
Min of monthly avg discharge: 1.1 cfs in 05/56
Drainage area: 109 square miles

MANATEE RIVER (Southern Region)

Total length: 45 miles
Headwaters: Four corners area Hillsborough, Polk, Hardee and manatee Counties.
Elevation: 130 feet
Mouth: Tampa Bay
Average fall: 2.9 feet/mile
Drainage area: 330 square miles

Myakka Head Station:

County: Manatee
Period-of-record: 1966
Location: 36 miles upstream from mouth
Avg daily discharge: 69.6 cfs
Runoff per year: 14.62 inches
Max of monthly avg discharge: 529.7 cfs in 09/1994
Min of monthly avg discharge: 0.5 cfs in 04/75
Drainage area: 65.3 square miles

MYAKKA RIVER (Southern Region)

Total length: 54.1 miles
Headwaters: Western Hardee and Eastern Manatee Counties
Tributaries: Howard Creek, Deer Prairie, and Big Slough Canal
Elevation: 105 feet
Mouth: Charlotte Harbor
Average fall: 1.9 feet/mile
Drainage area: 540 square miles

Sarasota Station:

County: Sarasota
Period-of-record: 1936
Location: 36 miles upstream from mouth
Avg daily discharge: 250.5 cfs
Runoff per year: 15.03 inches
Max of monthly avg discharge: 2467.2 cfs in 09/1947
Min of monthly avg discharge: 0.0 cfs numerous times
Drainage area: 229 square miles

PEACE RIVER (Central and Southern Region)

Total length: 120 miles
Headwaters: Green Swamp in northern Polk County through Lake Hancock, Winter Haven chain of lakes, and Lake Hamilton.
Tributaries: Peace Creek Canal, Saddle Creek, Charlie Creek, Prairie Creek, Horse Creek, Joshua Creek and Shell Creek. Elevation: 110 feet
Mouth: Charlotte Harbor
Average fall: 1 feet/mile
Drainage area: 2300 square miles


Arcadia Station (Southern Region):

County: Desoto
Period-of-record: 1931
Location: 36 miles upstream from mouth
Avg daily discharge: 1078.9 cfs
Runoff per year: 10.79 inches
Max of monthly avg discharge: 9876.0 cfs in 09/1933
Min of monthly avg discharge: 51.6 cfs 05/85
Drainage area: 1367 square miles

Bartow Station (Central Region):

County: Polk
Period-of-record: 1939
Location: 105 miles upstream from mouth
Avg daily discharge: 224.1 cfs
Runoff per year: 6.72 inches
Max of monthly avg discharge: 2261.5 cfs in 09/1960
Min of monthly avg discharge: 6.4 cfs 05/90
Drainage area: 390 square miles

Selected Spring Monitoring Stations



Selected Spring Monitoring Stations

<u>Map ID</u>	<u>Site Name</u>
1	Lithia Main Spring
2	Buckhorn Main Spring
3	Sulphur Springs at Sulphur Springs
5	Weeki Wachee River near Brooksville
6	Rainbow Springs near Dunnellon
7	Silver Springs near Ocala

SPRINGS MONITORING STATIONS

RAINBOW SPRINGS (Northern Region)

County:	Marion
Basin:	Withlacoochee River
Magnitude:	1 st
Discharge measurement location:	5 mi downstream from head of springs
Discharge contributes to:	Rainbow River, Withlacoochee River
Public Access:	Yes
Period-of-record:	1965
Gage:	Non-recording gage
Maximum daily mean:	1061 cfs in 09/1988
Minimum daily mean:	489 cfs in 06/2000

SILVER SPRINGS (Northern Region)

County:	Marion
Basin:	Ocklawaha River
Magnitude:	1 st
Discharge measurement location:	4 to 5 mi downstream from head of springs
Discharge contributes to:	Silver Springs River, Ocklawaha River, St. Johns River
Public Access:	Yes
Period-of-record:	1932
Gage:	Water-stage recorder
Maximum daily mean:	1290 cfs in 10/1960
Minimum daily mean:	432 cfs in 07/2000

WEEKI WACHEE SPRINGS (Northern Region)

County:	Hernando
Basin:	Coastal Rivers
Magnitude:	1 st
Discharge measurement location:	1 mi downstream from head of springs
Discharge contributes to:	Weeki Wachee River
Public Access:	Yes
Period-of-record:	1993
Gage:	Water-stage
Maximum daily mean:	229 cfs in 03/1998
Minimum daily mean:	101 cfs in 06/1994

SULPHUR SPRINGS (Central Region)

County:	Hillsborough
Basin:	Hillsborough River
Magnitude:	2 nd
Discharge measurement location:	300 ft downstream from gage
Discharge contributes to:	Hillsborough River
Public Access:	Yes
Period-of-record:	1956
Gage:	Water-stage recorder
Maximum daily mean:	145 cfs in 03/1960
Minimum daily mean:	0 cfs for various days throughout the period-of-record



BUCKHORN SPRINGS (Central Region)

County:	Hillsborough
Basin:	Alafia River
Magnitude:	2 nd
Discharge measurement location:	Difference between discharge measurements of Buckhorn Creek made 25 ft upstream from and 100 ft downstream from Buckhorn Springs
	Buckhorn Creek, Alafia River
Discharge contributes to:	No
Public Access:	No
Period-of-record:	1987
Gage:	Water-stage recorder
Maximum daily mean:	21.9 cfs in 02/1989
Minimum daily mean:	2.7 cfs in 06/1987

LITHIA SPRINGS: (Central Region)

County:	Hillsborough
Basin:	Alafia River
Magnitude:	2 nd
Discharge measurement location:	50 feet downstream from main pool
Discharge contributes to:	Alafia River
Public Access:	Yes
Period-of-record:	1934
Gage:	Water-stage recorder
Maximum daily mean:	83.4 cfs in 10/1967
Minimum daily mean:	6.3 cfs in 02/1989



Selected Surficial Aquifer Monitoring Stations



Selected Surficial Aquifer Monitoring Stations

<u>Map ID</u>	<u>Site Name</u>
1	State Road 33/Combee Road Shallow
2	Green Swamp L12B Shallow
3	ROMP 50 Surficial
4	State Road 577 Shallow
5	Lutz-Lake Fern Shallow
6	Lecanto 2 Shallow
7	Tarpon Road Shallow
~~8~~	~~Bairs Den Surficial~~
9	ROMP 26 Surficial
10	State Road 74 (77-Foot) Shallow
11	Loughman Shallow
12	USGS P-48 Shallow
13	Edgeville 4 Shallow



Selected Groundwater & Aquifer Resource Monitoring Stations





Select Groundwater & Aquifer Resource Monitoring Stations

Map ID	Site Name	Map ID	Site Name
1	Lake Alfred Deep nr Lake Alfred	49	ROMP 26 U Fldn Aq Monitor
2	ROMP 16 U Fldn Aq Monitor	50	SR 577 Deep
3	ROMP TR 21-2 U Fldn Aq Chloride Monitor	51	Debuel Road Deep
4	ROMP 87 U Fldn Aq (Avpk) Monitor	52	ROMP 103 U Fldn Aq Monitor
5	Pasco 13 nr Drexel Fldn	53	Webster City Fldn
6	Sanlon Ranch Fldn	54	Weeki Wachee Fldn Repl
7	ROMP 76 U Fldn Aq Monitor	55	Sarasota Service Office U Fldn Aq Monitor
8	ROMP 20 U Fldn Aq (Swnn) Monitor	56	Tidewater 1 Fldn
9	Edgeville 3 Deep	57	CE 14 Dunnellon Deep
10	Cargill FA-1 Fldn	58	DV-1 U Fldn Aq (Swnn) Monitor
11	ROMP TR 5-2 U Fldn Aq (Swnn) Monitor	59	ROMP 50 U Fldn Aq (Avpk) Chloride Monitor
12	Manasota 14 Deep	60	ROMP 40 U Fldn Aq Monitor
13	ROMP 116 U Fldn Aq Monitor	61	Masaryktown Deep
14	Big Slough Deep	62	ROMP 107 U Fldn Aq Monitor
15	Englewood 14 Deep	63	ROMP TR 10-2 U Fldn Aq Monitor
16	Loughman Deep	64	ROMP 48 U Fldn Aq (Tmpa/Swnn) Monitor
17	Coley Deep	65	ROMP 66 U Fldn Aq Monitor
18	Mascotte Deep (L-0062)	66	ROMP 31 U Fldn Aq Monitor
19	ROMP 59 U Fldn Aq Interface Monitor	67	ROMP 120 U Fldn Aq Monitor
20	ROMP 45 U Fldn Aq (Avpk) Monitor	68	ROMP 134 U Fldn Aq (Ocal-Avpk-Oldm) Monitor
21	ROMP TR 3-1 U Fldn Aq Monitor	69	ROMP TR 124 U Fldn Aq Monitor (Avpk) 2
22	ROMP 43XX U Fldn Aq Monitor	70	Moon Lake Deep
23	ROMP 32 U Fldn Aq (Avpk) Monitor	71	ROMP 89 U Fldn Aq Monitor
24	Verna Test 0-1	72	SR 52 Deep West nr Fivay Junction
25	ROMP 19X U Fldn Aq (Swnn) Monitor	73	Hillsborough River State Park Parking Lot Deep
26	ROMP 28X U Fldn Aq Monitor	74	ROMP TR 13-3 U Fldn Aq Monitor
27	ROMP TR 7-1 L Arca Aq Interface Monitor	75	ROMP TR 5-1 U Fldn Aq Sulfate Monitor
28	ROMP TR 1-2 U Fldn Aq Monitor	76	Kibler Deep
29	ROMP 17 U Fldn Aq (Swnn) Monitor	77	ROMP TR 7-4 U Fldn Aq (Swnn) Monitor
30	ROMP 58 U Fldn Aq Monitor	78	Marshall Deep (USGS)
31	ROMP 60 U Fldn Aq (Avpk) Monitor Repl	79	ROMP 111 U Fldn Aq Monitor
32	ROMP 22 U Fldn Aq (Swnn) Monitor	80	ROMP 19 U Fldn Aq (Swnn) Monitor
33	Sumter 13 JC 59 Up Fldn Repl	81	ROMP TR SA-1 U Fldn Aq (Swnn) Monitor
34	ROMP 9 U Fldn Aq (Swnn) Monitor	82	Florida Power Fldn at Piney Point
35	Tarpon Road Deep		
36	ROMP 123 Htrn As/U Fldn Aq Monitor		
37	ROMP 88 U Fldn Aq Monitor		
38	Inverness DOT Fldn		
39	Pinellas 665 Fldn		
40	Lykes Pasco Fldn		
41	ROMP 119 U Fldn Aq Sulfate Monitor		
42	SR 52 And CR 581 Deep		
43	ROMP 93 U Fldn Aq Monitor		
44	ROMP 30 U Fldn Aq Monitor		
45	ROMP 97 U Fldn Aq Monitor		
46	North Lecanto Deep		
47	Chassahowitzka 1 Deep		
48	Bexley 2 Fldn		

Wellfield Surficial Aquifer Monitoring Stations



Wellfield Groundwater Monitoring Stations



Wellfield Groundwater Monitoring Stations

<u>Map ID</u>	<u>Site Name</u>
1	Cypress Creek TMR-1 Deep
2	Cypress Creek TMR-3 Deep
3	Morris Bridge 3A Floridan
4	Cosme 3 Floridan
5	St. Pete Hillsboro 13 Deep
6	Eldridge-Wilde 11 Floridan
7	St. Pete 42 Deep
8	Cross Bar WRW Floridan
9	Eldridge-Wilde 2S Deep
10	State Road 54 Deep
11	Starkey Regional Floridan
12	Verna 08 Deep

Wellfield Surficial Aquifer Monitoring Stations

<u>Map ID</u>	<u>Site Name</u>
1	Cypress Creek TMR-1 Shallow
2	Morris Bridge 3A Surficial
3	Cypress Creek TMR-3 Shallow
4	St. Pete Hillsboro 13 Shallow
5	St. Pete IC-6 Shallow
6	Eldridge-Wilde 11 Surficial
7	Starkey 707 Shallow
8	Cross Bar SERW Shallow
9	State Road 54 Shallow

Reservoir Locations

